# SOUTH SUDAN HYDRO-CLIMATE WATCH

**21 Oct 2026 | Weekly version v191026**

ECMWF run 2026-10-20 12 UTC | rain and soil data to 2026-10-17 | 0 red, 46 orange, 23 yellow, 10 green counties

## Top 3 drought-watch counties

| County | Alert | Soil z | Soil deficit | Rain next 2 wk (median) | Chance 7-day dry spell |
|---|---|---|---|---|---|
| **Renk** (Upper Nile) | ORANGE | -3.38 | 39 mm | 0 mm | 100% |
| **Manyo** (Upper Nile) | ORANGE | -2.73 | 35 mm | 0 mm | 100% |
| **Pariang** (Unity) | ORANGE | -2.85 | 71 mm | 3 mm | 90% |

Lowest root-zone soil moisture that the next 2 weeks of rain will not fix.

## Top 3 flood-watch counties

| County | Alert | Soil z | 30-d surplus | Rain next 2 wk | Chance 50 mm wk 1 | People on flood-prone ground |
|---|---|---|---|---|---|---|
| **Bor South** (Jonglei) | ORANGE | -2.10 | 167 mm | 40 mm | 0% | 7,498 |
| **Lafon** (Eastern Equatoria) | ORANGE | -1.59 | 45 mm | 41 mm | 2% | 1,795 |
| **Twic East** (Jonglei) | ORANGE | -1.26 | 27 mm | 32 mm | 2% | 6,132 |

Wettest soil, water surplus and heavy rain ahead, weighted by people on flood-prone ground.

## 5 Gauge watch list

| Station | Last level | vs 2-yr level | Last 3 passes | Travel time | Warning left | Next station |
|---|---|---|---|---|---|---|
| Victoria Nile Trib01 km 5599 (hydroweb:100137) | 1047.86 m (2026-10-08) | below 2-yr by 0.19 m | rising +0.20 m | 14 d | 0 d | hydroweb:105851 |
| Victoria Nile km 5609 (hydroweb:107874) | 1034.98 m (2026-10-05) | below 2-yr by 0.09 m | steady/falling -0.17 m | 16 d | 0 d | hydroweb:105854 |
| Kibali km 3362 (hydroweb:3720) | 702.49 m (2026-10-16) | below 2-yr by 0.16 m | rising +1.38 m | 6 d | 1 d | hydroweb:4322 |
| ★ White Nile, River (dahiti:17750) | 411.70 m (2026-10-08) | above 2-yr by 0.06 m | steady/falling -0.11 m | 14 d | 1 d | dahiti:17749 |
| ★ Achwa Trib01 km 5388 (hydroweb:107879) | 1056.25 m (2026-09-08) | above 2-yr by 0.10 m | rising +0.49 m | 44 d | 1 d | hydroweb:106716 |

Travel time to the next station over 5 days and last pass newer than the travel time. ★ = station you already watch.

## 5 Towns and counties to monitor (red or orange, not in the lists above)

| Town / county | Alert | Soil z | Rain next 2 wk | Chance 50 mm wk 1 | Chance 7-day dry spell |
|---|---|---|---|---|---|
| Melut – Upper Nile | ORANGE | -2.13 | 1 mm | 0% | 100% |
| Maban – Upper Nile | ORANGE | -2.39 | 4 mm | 0% | 96% |
| Fashoda (Fashoda) – Upper Nile | ORANGE | -2.42 | 2 mm | 0% | 94% |
| Abyei Region – Abyei Region | ORANGE | -2.27 | 2 mm | 0% | 90% |
| Aweil North – Northern Bahr el Ghazal | ORANGE | -2.33 | 3 mm | 0% | 86% |

## Nile pulse countdown from Lake Victoria

| Point | Expected | Days left |
|---|---|---|
| Nimule | 01 Jan 2027 | 72 |
| Juba (Rejaf) | 10 Jan 2027 | 81 |

Lake Victoria 1135.84 m on 14 Oct (0.59 m below the May 2023 mean level (Hydroweb) of 1136.43 m).

Clock started 20 Sep 2026. Travel time of 103 days from the lake to Nimule and 9 more to Rejaf (Juba). Amber at 30 days, red at 10 days. If Lake Victoria reaches the May 2023 level, a second 30-day countdown to Juba starts. A travel-time estimate, not a river-level forecast.

## Countrywide and state-level news

• 17 Oct: **Lakes State:** Lakes State caretaker governor Rin Tueny Mabor, speaking in Rumbek, warned of possible hunger, saying May and June rainfall was insufficient for cultivation and rains that began in October came too late for this year's farming season; he said northern parts of the state face serious water and pasture shortages and cattle keepers may move herds towards southern Lakes and neighbouring areas (county not stated). (Eye Radio)
• 16 Oct: **Countrywide:** WFP's Matthew Hollingworth says the agency faces an $86 million funding gap now and a further $416 million gap over the next six months, and warns that more than one million vulnerable people could lose access to lifesaving food and nutrition assistance by October unless additional funding is secured; he says 7.8 million people struggle to find food each day as South Sudan faces conflict, displacement, economic hardship and

climate shocks. At Canal Pigi in Jonglei he met families whose farmland has stayed flooded seven years after the original floods, while drought affects the remaining land. (Eye Radio (WFP))
• 06 Oct: **Countrywide:** In a precautionary notice, the Ministry of Water Resources and Irrigation warns of possible Nile flooding in vulnerable areas in and around Juba: hydrological simulations suggest Lake Victoria could rise significantly, potentially above its historical maximum, and the notice cites ICPAC's outlook of a higher El Nino likelihood with above-normal rain over the Lake Victoria basin and parts of the wider Nile basin. Readings from Nimule to Renk and Nasir to Bentiu are decreasing and remain below flood-alert levels. Reduced June-September rainfall has also affected several states and the administrative areas of Abyei, Pibor and Ruweng. (Eye Radio)
News that names no county. County-level items are on each county page.

Open the live map: https://penuelabi.users.earthengine.app/view/south-sudan-weather-forecast
Subscribe to the email list:
https://docs.google.com/forms/d/e/1FAIpQLSeDtY-twsGL0Xx9FlK_nLjC9X_6FSt7QxzTa4NXJqztwRe5VA/viewform. To stop receiving it, unsubscribe here.

ALLAU, Denis Abi, PhD
Abuk Project
Mayardit Academy for Space Sciences
University of Juba and University of California, Davis
WhatsApp: +211 917 939 818
Email: penuelabi@gmail.com

Decision support, not an official warning. One page per county follows. Rainfall figures are an outlook for local flooding and access, not a river-level forecast.

# Contents

Counties by state. Click a county to jump to its page.


### Abyei Region (1)

Abyei Region 4

### Central Equatoria (6)

Juba 5
Kajo-keji 6
Lainya 7
Morobo 8
Terekeka 9
Yei 10

### Eastern Equatoria (8)

Budi 11
Ikotos 12
Kapoeta East 13
Kapoeta North 14
Kapoeta South 15
Lafon 16
Magwi 17
Torit 18

### Jonglei (11)

Akobo 19
Ayod 20
Bor South 21
Canal/Pigi 22
Duk 23
Fangak 24
Nyirol 25
Pibor 26
Pochalla 27
Twic East 28
Uror 29

### Lakes (8)

Awerial 30
Cueibet 31
Rumbek Centre 32
Rumbek East 33
Rumbek North 34
Wulu 35
Yirol East 36
Yirol West 37

### Northern Bahr el Ghazal (5)

Aweil Centre 38
Aweil East 39
Aweil North 40
Aweil South 41
Aweil West 42

### Unity (9)

Abiemnhom 43
Guit 44
Koch 45
Leer 46
Mayendit 47
Mayom 48
Panyijiar 49
Pariang 50
Rubkona 51

### Upper Nile (12)

Baliet 52
Fashoda 53
Longochuk 54
Luakpiny/Nasir 55
Maban 56
Maiwut 57
Malakal 58
Manyo 59
Melut 60
Panyikang 61
Renk 62
Ulang 63

### Warrap (6)

Gogrial East 64
Gogrial West 65
Tonj East 66
Tonj North 67
Tonj South 68
Twic 69

### Western Bahr el Ghazal (3)

Jur River 70
Raja 71
Wau 72

### Western Equatoria (10)

Ezo 73
Ibba 74
Maridi 75
Mundri East 76
Mundri West 77
Mvolo 78
Nagero 79
Nzara 80
Tambura 81
Yambio 82

# Abyei Region County

Abyei Region | County population about 145,358 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 64 mm below median in the top metre (30-day rain 109% of normal); ~2 mm expected over 2 weeks = 3% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (90%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 145,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | 24,468 | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 723 |
| 2 (planning) | 1,125 |
| 3 (severe) | 2,170 |
| Displaced in the planning case | 313 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Abyei Region | 10,496 | 6,736 | 3 (3) | 22 (22) | 6 (1) | 560.9 (372.2) |

Health facilities: 22 in the county, 22 on flood-prone ground | Schools: 3 in the county, 3 on flood-prone ground

## River level — nearest gauge: Bhar Al Arab km 4390

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: downstream of the county, about 15 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:7825 | Below 2-yr level | 394.42 m | 0th | -0.002 m/day | 2026-09-28 |

# Juba County

Central Equatoria | County population about 570,834 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 35 mm below median in the top metre (30-day rain 117% of normal); ~54 mm expected over 2 weeks = 154% of the deficit. Soils should recover if the rain arrives
• Exposure: About 3,000 people live on ground that has flooded before (of ~571,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 10,000 | not listed | 13,320 | 16,000 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 13,095 |
| 2 (planning) | 20,369 |
| 3 (severe) | 39,283 |
| Displaced in the planning case | 5,668 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Lobonok | 5,210 | 3,324 | 2 (1) | 5 (2) | 4,174 (36) | 263.2 (170.8) |
| Mangala South | 1,573 | 1,546 | 5 (5) | 2 (2) | 6,664 (142) | 123.1 (120.3) |
| Dolo | 1,835 | 1,471 | 6 (6) | 9 (6) | 4,058 (63) | 92.9 (76.9) |
| Mangala North | 1,262 | 1,246 | 0 (0) | 1 (1) | 4,430 (114) | 30.3 (29.8) |

Health facilities: 97 in the county, 63 on flood-prone ground | Schools: 73 in the county, 49 on flood-prone ground

## River station: White Nile km 4909 (hydroweb:7968)

### River level status

Latest pass 2026-10-14: **Above normal** (percentile 73). Level 452.47 m; seasonal median 452.02 m; anomaly +0.45 m. Record: min 450.66 m, max 453.08 m, average 451.91 m.
Baseline: 7 years, 15 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.10 m; 27 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| hydroweb:7853 | Above normal (percentile 68) on 2026-10-14 | 7 days | 2026-10-21 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| hydroweb:7857 | Near normal (percentile 38) on 2026-09-25 | 10 days | 2026-10-24 |

### Exposure within 25 km of the station

WorldPop population (2020): 76,550, of which 69,743 at risk. Schools: 45 (29 at risk). Health facilities: 58 (43 at risk). Buildings (VIDA): 507,411 (n/a at risk). Counties within 25 km: Juba, Terekeka.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Northern Bari (Juba) | 30,481 (28,346) | 213,829 | 3 (3) | 12 (10) |
| Gondokoro (Juba) | 19,337 (16,988) | 40,119 | 5 (5) | 2 (2) |
| Mangala South (Juba) | 15,822 (15,294) | 3,244 | 2 (2) | 2 (2) |
| Rejaf (Juba) | 4,301 (3,681) | 60,896 | 1 (1) | 4 (2) |

# Kajo-keji County

Central Equatoria | County population about 257,989 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 54 mm below median in the top metre (30-day rain 90% of normal); ~60 mm expected over 2 weeks = 112% of the deficit. Soils should recover if the rain arrives

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 3,656 |
| 2 (planning) | 5,687 |
| 3 (severe) | 10,968 |
| Displaced in the planning case | 1,583 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Liwolo | 1,155 | 628 | 13 (4) | 7 (1) | 3,889 (28) | 23.2 (11.2) |
| Kangapo II | 336 | 225 | 22 (8) | 14 (0) | 15,437 (163) | 0.0 (0.0) |
| Nyepo | 445 | 169 | 4 (0) | 6 (1) | 2,408 (7) | 27.2 (11.5) |
| Lire | 297 | 130 | 11 (5) | 8 (1) | 10,082 (95) | 17.8 (11.1) |

Health facilities: 43 in the county, 6 on flood-prone ground | Schools: 61 in the county, 21 on flood-prone ground

## River level — nearest gauge: Nile km 5018

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 0 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:203765 | Below 2-yr level | 509.94 m | 14th | -0.011 m/day | 2026-09-29 |

# Lainya County

Central Equatoria | County population about 119,155 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 47 mm below median in the top metre (30-day rain 106% of normal); ~71 mm expected over 2 weeks = 153% of the deficit. Soils should recover if the rain arrives
• Exposure: About 0 people live on ground that has flooded before (of ~119,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 446 |
| 2 (planning) | 693 |
| 3 (severe) | 1,337 |
| Displaced in the planning case | 193 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Mukaya | 1,628 | 1,139 | 15 (10) | 4 (1) | 4,750 (62) | 78.0 (58.2) |
| Lainya | 525 | 353 | 10 (3) | 6 (3) | 10,349 (178) | 33.9 (21.8) |
| Kupera | 478 | 320 | 5 (0) | 2 (2) | 1,836 (15) | 39.7 (26.2) |
| Wuji | 473 | 293 | 5 (3) | 4 (0) | 2,384 (24) | 36.6 (19.5) |

Health facilities: 21 in the county, 10 on flood-prone ground | Schools: 41 in the county, 18 on flood-prone ground

## River level — nearest gauge: Yei km 4848

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county’s own sub-basin, about 33 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:203361 | Below 2-yr level | 628.27 m | 0th | -0.014 m/day | 2026-10-10 |

# Morobo County

Central Equatoria | County population about 136,697 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 51 mm below median in the top metre (30-day rain 112% of normal); ~69 mm expected over 2 weeks = 136% of the deficit. Soils should recover if the rain arrives

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 464 |
| 2 (planning) | 721 |
| 3 (severe) | 1,391 |
| Displaced in the planning case | 201 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Panyume | 530 | 285 | 6 (1) | 2 (0) | 1,990 (24) | 1.8 (1.3) |
| Kimba | 194 | 95 | 9 (1) | 3 (2) | 8,854 (95) | 9.8 (3.1) |
| Wudabi | 219 | 88 | 8 (3) | 3 (0) | 2,418 (29) | 16.7 (7.5) |
| Lujulo | 186 | 85 | 10 (3) | 4 (1) | 1,284 (9) | 12.7 (5.4) |

Health facilities: 15 in the county, 3 on flood-prone ground | Schools: 50 in the county, 8 on flood-prone ground

## River level — nearest gauge: Nile km 5018

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 66 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:203765 | Below 2-yr level | 509.94 m | 14th | -0.011 m/day | 2026-09-29 |

# Terekeka County

Central Equatoria | County population about 266,693 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 63 mm below median in the top metre (30-day rain 144% of normal); ~44 mm expected over 2 weeks = 70% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Exposure: County population about 267,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | 8,503 | 8,505 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 2,471 |
| 2 (planning) | 3,843 |
| 3 (severe) | 7,412 |
| Displaced in the planning case | 1,069 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Rijong | 2,272 | 2,171 | 7 (7) | 4 (4) | 2,098 (25) | 201.8 (194.2) |
| Tali | 2,270 | 2,111 | 4 (4) | 10 (9) | 3,073 (55) | 195.3 (185.2) |
| Gameiza | 1,813 | 1,780 | 1 (1) | 2 (2) | 1,447 (38) | 77.3 (71.8) |
| Reggo | 1,394 | 1,364 | 3 (3) | 11 (11) | 3,757 (66) | 81.6 (80.5) |

Health facilities: 45 in the county, 43 on flood-prone ground | Schools: 27 in the county, 27 on flood-prone ground

## River station: White Nile km 4835 (hydroweb:7854)

### River level status

Latest pass 2026-10-14: **Above normal** (percentile 68). Level 435.81 m; seasonal median 435.39 m; anomaly +0.42 m. Record: min 434.25 m, max 436.36 m, average 435.31 m.
Baseline: 10 years, 22 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.05 m; 27 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| hydroweb:7967 | Near normal (percentile 64) on 2026-10-14 | 4 days | 2026-10-18 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| hydroweb:7966 | Near normal (percentile 64) on 2026-10-14 | 0 days | 2026-10-14 |

### Exposure within 25 km of the station

WorldPop population (2020): 57,125, of which 54,282 at risk. Schools: 10 (10 at risk). Health facilities: 17 (17 at risk). Buildings (VIDA): 17,467 (379 at risk). Counties within 25 km: Juba, Terekeka.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Gameiza (Terekeka) | 19,138 (18,130) | 1,119 | 0 (0) | 2 (2) |
| Terekeka (Terekeka) | 10,211 (9,226) | 6,763 | 6 (6) | 5 (5) |
| Reggo (Terekeka) | 10,197 (10,111) | 1,584 | 2 (2) | 5 (5) |
| Muni (Terekeka) | 7,014 (6,679) | 5,580 | 2 (2) | 4 (4) |

# Yei County

Central Equatoria | County population about 327,602 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 48 mm below median in the top metre (30-day rain 101% of normal); ~71 mm expected over 2 weeks = 148% of the deficit. Soils should recover if the rain arrives
• Exposure: About 0 people live on ground that has flooded before (of ~328,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 1,219 |
| 2 (planning) | 1,896 |
| 3 (severe) | 3,657 |
| Displaced in the planning case | 528 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Tore | 4,088 | 2,483 | 15 (8) | 6 (4) | 4,335 (91) | 237.5 (153.8) |
| Lasu | 1,073 | 714 | 10 (6) | 5 (3) | 6,745 (109) | 39.2 (25.8) |
| Yei | 559 | 395 | 22 (12) | 13 (6) | 61,160 (n/a) | 45.0 (33.1) |
| Otogo | 513 | 369 | 13 (4) | 10 (4) | 9,916 (145) | 51.5 (40.3) |

Health facilities: 39 in the county, 18 on flood-prone ground | Schools: 77 in the county, 36 on flood-prone ground

## River level — nearest gauge: Yei km 4848

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county’s own sub-basin, about 35 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:203361 | Below 2-yr level | 628.27 m | 0th | -0.014 m/day | 2026-10-10 |

# Budi County

Eastern Equatoria | County population about 108,474 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 50 mm below median in the top metre (30-day rain 60% of normal); ~44 mm expected over 2 weeks = 88% of the deficit. Soils should recover if the rain arrives

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 407 |
| 2 (planning) | 633 |
| 3 (severe) | 1,221 |
| Displaced in the planning case | 176 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Komori | 1,890 | 878 | 6 (1) | 6 (3) | 6,591 (48) | 85.1 (32.0) |
| Loriyok | 1,304 | 757 | 2 (2) | 3 (3) | 1,470 (26) | 72.2 (52.9) |
| Napak | 595 | 426 | 0 (0) | 1 (1) | 654 (7) | 42.7 (26.7) |
| Kimotong | 470 | 290 | 0 (0) | 1 (0) | 704 (10) | 37.1 (26.8) |

Health facilities: 21 in the county, 9 on flood-prone ground | Schools: 8 in the county, 3 on flood-prone ground

## River level — nearest gauge: Pager km 5350

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 88 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:102552 | Below 2-yr level | 974.45 m | 0th | -0.023 m/day | 2026-09-25 |

# Ikotos County

Eastern Equatoria | County population about 111,148 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 52 mm below median in the top metre (30-day rain 65% of normal); ~46 mm expected over 2 weeks = 87% of the deficit. Soils should recover if the rain arrives

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 413 |
| 2 (planning) | 643 |
| 3 (severe) | 1,240 |
| Displaced in the planning case | 179 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Losite | 1,048 | 751 | 4 (3) | 5 (1) | 2,152 (3) | 21.5 (16.9) |
| Ikotos | 842 | 489 | 4 (2) | 5 (3) | 6,319 (84) | 103.4 (61.4) |
| Lomohidang North | 367 | 238 | 5 (3) | 3 (1) | 2,726 (29) | 38.2 (25.9) |
| Imotong | 212 | 169 | 0 (0) | 2 (0) | 1,224 (5) | 15.4 (6.4) |

Health facilities: 21 in the county, 6 on flood-prone ground | Schools: 20 in the county, 8 on flood-prone ground

## River level — nearest gauge: Pager km 5350

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 66 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:102552 | Below 2-yr level | 974.45 m | 0th | -0.023 m/day | 2026-09-25 |

# Kapoeta East County

Eastern Equatoria | County population about 175,078 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 40 mm below median in the top metre (30-day rain 65% of normal); ~36 mm expected over 2 weeks = 90% of the deficit. Soils should recover if the rain arrives

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 658 |
| 2 (planning) | 1,023 |
| 3 (severe) | 1,973 |
| Displaced in the planning case | 285 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Jie | 2,927 | 1,955 | 0 (0) | 1 (1) | 2,141 (42) | 226.8 (172.2) |
| Kauto | 7,471 | 1,716 | 0 (0) | 2 (0) | 10,963 (47) | 348.1 (79.1) |
| Narus | 9,603 | 872 | 12 (1) | 7 (1) | 10,318 (51) | 673.7 (30.3) |
| Mogos | 2,047 | 815 | 0 (0) | 1 (1) | 3,123 (35) | 181.3 (92.3) |

Health facilities: 18 in the county, 4 on flood-prone ground | Schools: 17 in the county, 2 on flood-prone ground

## River level — nearest gauge: Pibor km 4625

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: downstream of the county, about 151 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:101872 | Below 2-yr level | 405.52 m | 0th | -0.028 m/day | 2026-09-21 |

# Kapoeta North County

Eastern Equatoria | County population about 162,158 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 63 mm below median in the top metre (30-day rain 72% of normal); ~38 mm expected over 2 weeks = 60% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Exposure: County population about 162,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 601 |
| 2 (planning) | 935 |
| 3 (severe) | 1,803 |
| Displaced in the planning case | 260 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Karukomuge | 4,520 | 2,836 | 2 (2) | 8 (6) | 1,274 (13) | 91.4 (56.5) |
| Lomeyen | 580 | 457 | 1 (1) | 3 (3) | 1,800 (25) | 16.3 (11.4) |
| Mosingo | 271 | 145 | 1 (1) | 0 (0) | 2,619 (26) | 7.9 (4.6) |
| Paringa | 190 | 94 | 1 (1) | 2 (2) | 1,430 (22) | 9.0 (7.8) |

Health facilities: 16 in the county, 14 on flood-prone ground | Schools: 10 in the county, 10 on flood-prone ground

## River level — nearest gauge: Pibor km 4625

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: downstream of the county, about 127 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:101872 | Below 2-yr level | 405.52 m | 0th | -0.028 m/day | 2026-09-21 |

# Kapoeta South County

Eastern Equatoria | County population about 105,511 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 46 mm below median in the top metre (30-day rain 51% of normal); ~34 mm expected over 2 weeks = 74% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Exposure: County population about 106,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 433 |
| 2 (planning) | 674 |
| 3 (severe) | 1,300 |
| Displaced in the planning case | 188 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Machi One | 143 | 79 | 0 (0) | 4 (3) | 2,362 (33) | 16.6 (8.8) |
| Machi Two | 117 | 62 | 0 (0) | 1 (1) | 2,104 (22) | 17.4 (9.4) |
| Kapoeta Town | 114 | 62 | 1 (1) | 4 (4) | 7,639 (299) | 24.4 (10.6) |
| Longeleya | 132 | 45 | 4 (4) | 0 (0) | 2,645 (28) | 15.0 (6.7) |

Health facilities: 10 in the county, 9 on flood-prone ground | Schools: 9 in the county, 8 on flood-prone ground

## River level — nearest gauge: Pager km 5355

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: nearest gauge (different sub-basin), about 134 km away (indicative confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:106718 | Below 2-yr level | 964.90 m | 0th | +0.001 m/day | 2026-09-29 |

# Lafon County

Eastern Equatoria | County population about 163,767 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 63 mm below median in the top metre (30-day rain 107% of normal); ~41 mm expected over 2 weeks = 64% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Exposure: County population about 164,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | 18,178 | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 622 |
| 2 (planning) | 968 |
| 3 (severe) | 1,867 |
| Displaced in the planning case | 269 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Burgilo | 10,443 | 9,664 | 5 (4) | 2 (2) | 2,652 (48) | 73.1 (63.6) |
| Arihilo | 1,506 | 1,155 | 1 (0) | 4 (0) | 2,235 (3) | 104.0 (78.1) |
| Pachidi | 1,232 | 1,091 | 6 (4) | 3 (3) | 671 (12) | 109.8 (88.2) |
| Marguna | 961 | 932 | 2 (2) | 2 (2) | 907 (20) | 85.9 (82.3) |

Health facilities: 24 in the county, 14 on flood-prone ground | Schools: 30 in the county, 17 on flood-prone ground

## River level — nearest gauge: Nile km 4826

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 33 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:201328 | Below 2-yr level | 434.37 m | 29th | -0.012 m/day | 2026-09-29 |

# Magwi County

Eastern Equatoria | County population about 314,109 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 65 mm below median in the top metre (30-day rain 79% of normal); ~62 mm expected over 2 weeks = 95% of the deficit. Soils should recover if the rain arrives

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 2,537 | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 1,084 |
| 2 (planning) | 1,686 |
| 3 (severe) | 3,252 |
| Displaced in the planning case | 469 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Pageri | 2,301 | 1,432 | 29 (7) | 16 (4) | 5,956 (75) | 123.5 (69.8) |
| Magwi | 1,167 | 674 | 38 (15) | 12 (1) | 10,051 (123) | 80.5 (37.8) |
| Pajok | 825 | 521 | 20 (6) | 8 (5) | 3,937 (85) | 25.4 (7.6) |
| Mugali | 262 | 194 | 14 (3) | 6 (3) | 1,702 (10) | 0.0 (0.0) |

Health facilities: 46 in the county, 15 on flood-prone ground | Schools: 146 in the county, 58 on flood-prone ground

## River station: Bahr Al Jabal km 5093 (hydroweb:112211)

### River level status

Latest pass 2026-10-14: **Near normal** (percentile 52). Level 615.48 m; seasonal median 615.47 m; anomaly +0.01 m. Record: min 614.86 m, max 616.31 m, average 615.49 m.

Baseline: 5 years, 27 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.13 m; 10 days since previous pass.

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| hydroweb:101187 | Near normal (percentile 50) on 2026-10-14 | 14 days | 2026-10-28 |

### Exposure within 25 km of the station

WorldPop population (2020): 253,110, of which 139,520 at risk. Schools: 68 (31 at risk). Health facilities: 13 (5 at risk). Buildings (VIDA): 26,468 (557 at risk). Counties within 25 km: Magwi.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Pageri (Magwi) | 85,252 (50,691) | 1,022 | 13 (4) | 4 (0) |
| Nimule (Magwi) | 68,159 (37,797) | 23,754 | 40 (24) | 3 (2) |
| Mugali (Magwi) | 37,242 (27,564) | 1,692 | 14 (3) | 6 (3) |

# Torit County

Eastern Equatoria | County population about 65,844 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 53 mm below median in the top metre (30-day rain 84% of normal); ~52 mm expected over 2 weeks = 98% of the deficit. Soils should recover if the rain arrives
• Exposure: About 0 people live on ground that has flooded before (of ~66,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 275 |
| 2 (planning) | 427 |
| 3 (severe) | 824 |
| Displaced in the planning case | 119 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Bur | 1,100 | 1,033 | 12 (12) | 8 (7) | 2,487 (57) | 76.3 (69.5) |
| Hiyala | 1,246 | 1,022 | 35 (28) | 13 (8) | 5,717 (103) | 85.3 (70.0) |
| Kudo | 1,077 | 643 | 7 (4) | 6 (2) | 2,585 (40) | 66.7 (48.0) |
| Imurok | 646 | 340 | 14 (6) | 3 (3) | 1,023 (23) | 72.5 (50.2) |

Health facilities: 41 in the county, 27 on flood-prone ground | Schools: 141 in the county, 100 on flood-prone ground

## River level — nearest gauge: White Nile km 4934

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 53 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:7853 | Above 2-yr level | 459.35 m | 67th | -0.025 m/day | 2026-10-04 |

# Akobo County

Jonglei | County population about 238,042 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 95 mm below median in the top metre (30-day rain 99% of normal); ~23 mm expected over 2 weeks = 24% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Exposure: County population about 238,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 13,986 | not listed | 97,730 | 17,652 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 10,941 |
| 2 (planning) | 17,020 |
| 3 (severe) | 32,824 |
| Displaced in the planning case | 4,736 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Diror | 2,532 | 2,472 | 1 (1) | 4 (4) | 2,247 (48) | 134.1 (132.8) |
| Nyandit | 2,469 | 2,368 | 6 (6) | 3 (3) | 643 (24) | 149.7 (135.9) |
| Bilkey | 1,383 | 1,362 | 8 (8) | 2 (1) | 8,744 (235) | 125.1 (121.6) |
| Dengjok | 962 | 950 | 4 (4) | 4 (4) | 1,456 (39) | 65.4 (64.3) |

Health facilities: 18 in the county, 17 on flood-prone ground | Schools: 25 in the county, 25 on flood-prone ground

## River level — nearest gauge: Pipor, River

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: upstream of the county, about 0 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| dahiti:23353 | Below 2-yr level | 402.24 m | 0th | +0.007 m/day | 2026-10-09 |

# Ayod County

Jonglei | County population about 205,709 | Issued 21 October 2026

## Advisory

- No significant change expected: near normal soils, about 9 mm of rain in week 1
- Exposure: About 7,000 people live on ground that has flooded before (of ~206,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 55,000 | not listed | 26,700 | 57,270 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 18,552 |
| 2 (planning) | 28,858 |
| 3 (severe) | 55,655 |
| Displaced in the planning case | 8,030 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Settlements assessed Sept 2025

| Payam | Settlements | People | Flooded | High ground | Small towns |
|---|---|---|---|---|---|
| Ayod | 2 | 1,800 | 0 | 1,000 | 800 |
| Kuach-deng | 3 | 24,300 | 0 | 8,300 | 16,000 |
| Kurwai | 2 | 800 | 800 | 0 | 0 |
| Mogok | 2 | 3,800 | 0 | 2,400 | 1,400 |
| Pagil | 6 | 24,100 | 22,500 | 0 | 1,600 |
| Pajiek | 6 | 12,200 | 8,500 | 2,000 | 1,700 |
| Wau | 1 | 700 | 0 | 700 | 0 |
| **Ayod County** | **22** | **67,700** | **31,800** | **14,400** | **21,500** |

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Pajiek | 4,026 | 2,797 | 3 (3) | 3 (3) | 4,038 (132) | 174.5 (135.5) |
| Kurwai | 2,375 | 2,147 | 7 (7) | 4 (4) | 1,523 (55) | 11.8 (11.2) |
| Mogok | 1,906 | 1,882 | 4 (4) | 3 (3) | 1,993 (77) | 112.5 (110.9) |
| Wau | 2,279 | 1,841 | 2 (2) | 0 (0) | 2,181 (63) | 103.4 (95.5) |

Health facilities: 11 in the county, 11 on flood-prone ground | Schools: 23 in the county, 23 on flood-prone ground

## River station: White Nile km 4336 (hydroweb:7874)

### River level status

Latest pass 2026-10-14: **Above normal** (percentile 89). Level 399.18 m; seasonal median 399.10 m; anomaly +0.08 m. Record: min 398.69 m, max 399.26 m, average 399.03 m.

Baseline: 10 years, 61 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.01 m; 10 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| hydroweb:7875 | Below normal (percentile 33) on 2026-10-14 | 3 days | 2026-10-17 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| hydroweb:7900 | Above normal (percentile 69) on 2026-10-16 | 21 days | 2026-11-04 |

### Exposure within 25 km of the station

WorldPop population (2020): 67,944, of which 56,207 at risk. Schools: 17 (17 at risk). Health facilities: 10 (10 at risk). Buildings (VIDA): 11,943 (313 at risk). Counties within 25 km: Ayod, Leer, Mayendit.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Yang (Leer) | 16,007 (12,093) | 2,034 | 2 (2) | 1 (1) |
| Wau (Ayod) | 13,032 (9,261) | 23 | 0 (0) | 0 (0) |
| Adok (Leer) | 12,778 (10,480) | 3,952 | 10 (10) | 2 (2) |
| Padeah (Leer) | 9,554 (8,920) | 1,108 | 3 (3) | 1 (1) |

# Bor South County

Jonglei | County population about 354,711 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 134 mm below median in the top metre (30-day rain 151% of normal); ~41 mm expected over 2 weeks = 30% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Exposure: County population about 355,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 42,051 | not listed | 2,946 | 76,000 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 28,774 |
| 2 (planning) | 44,760 |
| 3 (severe) | 86,323 |
| Displaced in the planning case | 12,455 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Baidit | 4,477 | 4,358 | 25 (23) | 4 (4) | 4,968 (154) | 54.1 (47.2) |
| Makuach | 3,301 | 3,262 | 11 (8) | 1 (1) | 2,060 (60) | 32.5 (29.5) |
| Kolnyang | 3,155 | 3,126 | 20 (20) | 6 (5) | 11,318 (353) | 156.9 (153.2) |
| Anyidi | 1,823 | 1,821 | 8 (8) | 2 (2) | 960 (29) | 111.3 (111.3) |

Health facilities: 33 in the county, 31 on flood-prone ground | Schools: 142 in the county, 136 on flood-prone ground

## River station: White Nile, River (dahiti:17754)

### River level status

Latest pass 2026-09-25: **Unusually high** (percentile 100). Level 422.61 m; seasonal median 422.32 m; anomaly +0.29 m. Record: min 421.06 m, max 422.63 m, average 422.01 m.

Baseline: 7 years, 14 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.00 m; 27 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| dahiti:17753 | Below normal (percentile 31) on 2026-08-31 | 2 days | 2026-09-02 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| dahiti:3246 | Above normal (percentile 68) on 2026-09-04 | 6 days | 2026-10-01 |

### Exposure within 25 km of the station

WorldPop population (2020): 50,867, of which 40,580 at risk. Schools: 99 (93 at risk). Health facilities: 23 (22 at risk). Buildings (VIDA): 62,858 (n/a at risk). Counties within 25 km: Awerial, Bor South, Yirol East.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Baidit (Bor South) | 20,075 (15,509) | 3,976 | 25 (23) | 4 (4) |
| Bor (Bor South) | 10,017 (9,061) | 57,396 | 64 (62) | 16 (15) |
| Nile (Awerial) | 7,158 (5,355) | 257 | 1 (1) | 0 (0) |
| Makuach (Bor South) | 5,110 (4,352) | 699 | 8 (6) | 1 (1) |

# Canal/Pigi County

Jonglei | County population about 111,613 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 67 mm below median in the top metre (30-day rain 134% of normal); ~7 mm expected over 2 weeks = 10% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell possible (56%) on dry soils: monitor crops and pasture
• Exposure: County population about 112,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 35,462 | not listed | 39,971 | 25,500 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 9,699 |
| 2 (planning) | 15,088 |
| 3 (severe) | 29,098 |
| Displaced in the planning case | 4,198 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Alam | 1,287 | 1,159 | 0 (0) | 0 (0) | 242 (7) | 74.3 (68.0) |
| Wunlem | 1,003 | 901 | 1 (0) | 0 (0) | 38 (0) | 63.4 (52.9) |
| Mareng | 778 | 318 | 9 (2) | 0 (0) | 134 (2) | 76.6 (33.7) |
| Atar | 724 | 111 | 7 (0) | 5 (0) | 1,830 (0) | 56.9 (4.1) |

Health facilities: 12 in the county, 1 on flood-prone ground | Schools: 36 in the county, 7 on flood-prone ground

## River station: White Nile km 4029 (hydroweb:7965)

### River level status

Latest pass 2026-10-12: **Above normal** (percentile 72). Level 390.60 m; seasonal median 389.83 m; anomaly +0.77 m. Record: min 387.81 m, max 391.52 m, average 389.65 m.

Baseline: 8 years, 18 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.02 m; 27 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| hydroweb:7886 | Near normal (percentile 50) on 2026-09-23 | 0 days | 2026-09-23 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| hydroweb:7895 | Near normal (percentile 56) on 2026-09-29 | 1 days | 2026-10-13 |

### Exposure within 25 km of the station

WorldPop population (2020): 61,010, of which 23,270 at risk. Schools: 14 (1 at risk). Health facilities: 17 (2 at risk). Buildings (VIDA): 5,349 (26 at risk). Counties within 25 km: Canal/Pigi, Fangak, Panyikang.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Atar (Canal/Pigi) | 24,728 (7,503) | 1,755 | 3 (0) | 4 (0) |
| Korwach (Canal/Pigi) | 12,961 (3,013) | 610 | 11 (1) | 3 (0) |
| Panyikang (Panyikang) | 8,100 (5,666) | 587 | 0 (0) | 2 (0) |
| Manajang (Fangak) | 5,141 (1,598) | 1,011 | 0 (0) | 2 (0) |

# Duk County

Jonglei | County population about 206,545 | Issued 21 October 2026

## Advisory

- No significant change expected: dry soils, about 13 mm of rain in week 1
- Exposure: About 5,000 people live on ground that has flooded before (of ~207,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 45,000 | not listed | 16,771 | 22,548 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 13,231 |
| 2 (planning) | 20,582 |
| 3 (severe) | 39,694 |
| Displaced in the planning case | 5,727 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Settlements assessed Sept 2025

| Payam | Settlements | People | Flooded | High ground | Small towns |
|---|---|---|---|---|---|
| Ageer | 1 | 2,200 | 0 | 2,200 | 0 |
| Dongchak | 3 | 2,600 | 1,300 | 1,300 | 0 |
| Padiet | 4 | 39,500 | 1,000 | 9,600 | 28,900 |
| Pagak | 4 | 12,000 | 1,800 | 5,700 | 4,500 |
| Panyang | 3 | 9,100 | 0 | 6,200 | 2,900 |
| Payuel | 4 | 23,100 | 0 | 12,300 | 10,800 |
| **Duk County** | **19** | **88,500** | **4,100** | **37,300** | **47,100** |

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Dongchak | 3,316 | 2,089 | 1 (1) | 2 (2) | 1,038 (26) | 129.6 (102.3) |
| Panyang | 872 | 852 | 4 (4) | 3 (3) | 1,201 (34) | 87.4 (83.8) |
| Ageer | 932 | 731 | 2 (0) | 2 (2) | 835 (13) | 45.3 (32.5) |
| Pagak | 680 | 679 | 0 (0) | 1 (1) | 424 (12) | 15.2 (15.2) |

Health facilities: 14 in the county, 14 on flood-prone ground | Schools: 11 in the county, 9 on flood-prone ground

## River level — nearest gauge: White Nile km 4500

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 0 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:7877 | Below 2-yr level | 407.48 m | 26th | +0.025 m/day | 2026-10-14 |

# Fangak County

Jonglei | County population about 213,029 | Issued 21 October 2026

## Advisory

- No significant change expected: near normal soils, about 5 mm of rain in week 1
- Exposure: About 5,000 people live on ground that has flooded before (of ~213,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 73,191 | 17,669 | 154,005 | 145,316 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 36,008 |
| 2 (planning) | 56,013 |
| 3 (severe) | 108,025 |
| Displaced in the planning case | 15,586 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Settlements assessed Sept 2025

| Payam | Settlements | People | Flooded | High ground | Small towns |
|---|---|---|---|---|---|
| Manajang | 10 | 27,300 | 7,000 | 0 | 20,300 |
| Mareang | 3 | 9,140 | 600 | 0 | 8,540 |
| Old Fangak | 2 | 3,000 | 3,000 | 0 | 0 |
| Paguir | 4 | 17,360 | 1,100 | 0 | 16,260 |
| Phom | 1 | 0 | 0 | 0 | 0 |
| **Fangak County** | **20** | **56,800** | **11,700** | **0** | **45,100** |

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Paguir | 3,008 | 2,645 | 7 (4) | 6 (4) | 5,223 (120) | 57.8 (45.0) |
| Mareang | 1,742 | 1,623 | 5 (5) | 2 (2) | 420 (18) | 0.0 (0.0) |
| Old Fangak | 1,659 | 1,387 | 4 (4) | 0 (0) | 1,979 (57) | 79.7 (72.0) |
| Manajang | 1,224 | 348 | 8 (1) | 7 (1) | 8,254 (12) | 84.2 (14.3) |

Health facilities: 18 in the county, 7 on flood-prone ground | Schools: 24 in the county, 14 on flood-prone ground

## River station: Bahr El Zeraf km 4110 (hydroweb:105860)

### River level status

Latest pass 2026-09-25: **Above normal** (percentile 69). Level 393.28 m; seasonal median 393.17 m; anomaly +0.11 m. Record: min 391.28 m, max 393.93 m, average 392.82 m.

Baseline: 7 years, 16 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.04 m; 27 days since previous pass.

### Routed downstream signal

No downstream station linked.

### Exposure within 25 km of the station

WorldPop population (2020): 36,373, of which 29,341 at risk. Schools: 13 (13 at risk). Health facilities: 5 (3 at risk). Buildings (VIDA): 6,583 (169 at risk). Counties within 25 km: Fangak.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Old Fangak (Fangak) | 18,363 (16,152) | 1,799 | 4 (4) | 0 (0) |
| Paguir (Fangak) | 9,354 (7,958) | 3,071 | 4 (4) | 2 (2) |
| Manajang (Fangak) | 4,379 (1,029) | 1,578 | 1 (1) | 2 (0) |
| Mareang (Fangak) | 4,277 (4,202) | 136 | 4 (4) | 1 (1) |

# Nyirol County

Jonglei | County population about 153,295 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 103 mm below median in the top metre (30-day rain 111% of normal); ~14 mm expected over 2 weeks = 13% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell possible (38%) on dry soils: monitor crops and pasture
• Exposure: County population about 153,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 8,832 | 0 | 16,500 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 9,578 |
| 2 (planning) | 14,899 |
| 3 (severe) | 28,734 |
| Displaced in the planning case | 4,146 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Thol | 2,672 | 2,518 | 14 (13) | 3 (3) | 6,422 (142) | 104.0 (95.7) |
| Chuil | 1,453 | 1,218 | 0 (0) | 0 (0) | 1,727 (35) | 30.2 (27.6) |
| Pulturuk | 1,069 | 1,039 | 5 (5) | 2 (2) | 345 (11) | 40.4 (39.7) |
| Nyambor | 881 | 864 | 6 (6) | 1 (1) | 203 (5) | 36.4 (35.5) |

Health facilities: 9 in the county, 9 on flood-prone ground | Schools: 36 in the county, 35 on flood-prone ground

## River level — nearest gauge: Fulus km 4165

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county's own sub-basin, about 0 km away (high confidence). Altimetry levels are "as seen by satellite" — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:106193 | Stale (last pass 77 d ago) | 392.98 m | 0th | +0.000 m/day | 2026-08-04 |

# Pibor County

Jonglei | County population about 237,649 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 67 mm below median in the top metre (30-day rain 97% of normal); ~40 mm expected over 2 weeks = 60% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Exposure: County population about 238,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | 0 | 146,851 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 35,634 |
| 2 (planning) | 55,430 |
| 3 (severe) | 106,901 |
| Displaced in the planning case | 15,424 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Verteth | 7,791 | 7,515 | 0 (0) | 0 (0) | 1,561 (34) | 110.7 (84.9) |
| Kiziongora | 6,669 | 6,093 | 0 (0) | 5 (4) | 3,800 (48) | 233.9 (210.2) |
| Gumuruk | 4,471 | 4,414 | 0 (0) | 1 (1) | 10,677 (260) | 174.6 (167.6) |
| Pibor | 3,613 | 3,382 | 7 (7) | 1 (1) | 8,098 (193) | 182.6 (165.8) |

Health facilities: 15 in the county, 10 on flood-prone ground | Schools: 8 in the county, 8 on flood-prone ground

## River level — nearest gauge: Lotilla km 4712

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: upstream of the county, about 0 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:7909 | Below 2-yr level | 410.75 m | 0th | -0.009 m/day | 2026-09-21 |

# Pochalla County

Jonglei | County population about 82,568 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 79 mm below median in the top metre (30-day rain 78% of normal); ~34 mm expected over 2 weeks = 43% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Exposure: County population about 83,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 31,326 | 15,335 | 22,477 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 4,234 |
| 2 (planning) | 6,586 |
| 3 (severe) | 12,702 |
| Displaced in the planning case | 1,833 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Pochalla | 3,089 | 2,967 | 3 (3) | 4 (3) | 2,143 (40) | 170.5 (167.7) |
| Adongo | 2,681 | 2,447 | 4 (4) | 3 (3) | 1,941 (25) | 178.1 (160.4) |
| Omiela | 1,033 | 844 | 1 (1) | 0 (0) | 108 (3) | 69.9 (47.5) |
| Burator | 950 | 842 | 1 (1) | 0 (0) | 357 (10) | 37.0 (31.6) |

Health facilities: 8 in the county, 7 on flood-prone ground | Schools: 9 in the county, 9 on flood-prone ground

## River level — nearest gauge: Baro Trib 01 km 4483

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 15 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:102319 | Below 2-yr level | 409.70 m | 29th | +0.002 m/day | 2026-09-23 |

# Twic East County

Jonglei | County population about 129,822 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 86 mm below median in the top metre (30-day rain 110% of normal); ~32 mm expected over 2 weeks = 38% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Exposure: County population about 130,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 58,069 | not listed | 55,349 | 101,675 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 23,245 |
| 2 (planning) | 36,159 |
| 3 (severe) | 69,735 |
| Displaced in the planning case | 10,062 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Settlements assessed Sept 2025

| Payam | Settlements | People | Flooded | High ground | Small towns |
|---|---|---|---|---|---|
| Ajuong | 1 | 11,100 | 0 | 0 | 11,100 |
| Kongor | 2 | 21,300 | 0 | 0 | 21,300 |
| Lith | 3 | 10,950 | 9,200 | 0 | 1,750 |
| Nyuak | 3 | 16,800 | 1,600 | 2,200 | 13,000 |
| Pakeer | 2 | 14,900 | 1,300 | 0 | 13,600 |
| **Twic East County** | **11** | **75,050** | **12,100** | **2,200** | **60,750** |

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Pakeer | 1,326 | 1,203 | 5 (5) | 2 (2) | 2,033 (69) | 82.7 (80.7) |
| Ajuong | 1,859 | 1,183 | 2 (2) | 1 (1) | 1,301 (40) | 18.4 (18.4) |
| Lith | 1,181 | 1,140 | 3 (3) | 1 (1) | 213 (8) | 94.5 (86.2) |
| Nyuak | 1,113 | 1,091 | 6 (6) | 2 (2) | 5,498 (184) | 89.9 (87.7) |

Health facilities: 8 in the county, 8 on flood-prone ground | Schools: 21 in the county, 21 on flood-prone ground

## River station: White Nile, River (dahiti:17749)

### River level status

Latest pass 2026-09-23: **Unusually high** (percentile 94). Level 410.11 m; seasonal median 409.89 m; anomaly +0.21 m. Record: min 409.20 m, max 410.24 m, average 409.74 m.

Baseline: 7 years, 16 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.02 m; 27 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| dahiti:17750 | Near normal (percentile 45) on 2026-10-08 | 14 days | 2026-10-22 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| dahiti:15557 | Unusually high (percentile 93) on 2026-09-25 | 49 days | 2026-11-11 |

### Exposure within 25 km of the station

WorldPop population (2020): 23,275, of which 13,714 at risk. Schools: 1 (1 at risk). Health facilities: 1 (0 at risk). Buildings (VIDA): 347 (7 at risk). Counties within 25 km: Duk, Panyijiar, Twic East, Yirol East.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Ajuong (Twic East) | 8,844 (3,536) | 98 | 0 (0) | 0 (0) |
| Adior (Yirol East) | 6,863 (4,796) | 211 | 0 (0) | 1 (0) |
| Pachienjok (Panyijiar) | 2,646 (1,684) | 3 | 1 (1) | 0 (0) |
| Tinagau (Yirol East) | 2,305 (2,292) | 9 | 0 (0) | 0 (0) |

# Uror County

Jonglei | County population about 205,594 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 122 mm below median in the top metre (30-day rain 133% of normal); ~24 mm expected over 2 weeks = 20% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Exposure: County population about 206,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | 24,516 | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 771 |
| 2 (planning) | 1,200 |
| 3 (severe) | 2,314 |
| Displaced in the planning case | 334 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Pieri | 4,609 | 4,606 | 8 (8) | 2 (2) | 2,324 (65) | 181.6 (181.4) |
| Payai | 3,307 | 3,304 | 2 (2) | 1 (1) | 981 (39) | 101.2 (100.5) |
| Tiam | 2,036 | 2,034 | 1 (1) | 1 (1) | 2,431 (69) | 67.0 (67.0) |
| Pathai | 773 | 767 | 1 (1) | 2 (2) | 2,153 (61) | 94.1 (94.0) |

Health facilities: 10 in the county, 10 on flood-prone ground | Schools: 23 in the county, 23 on flood-prone ground

## River level — nearest gauge: Fulus km 4188

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county's own sub-basin, about 25 km away (high confidence). Altimetry levels are "as seen by satellite" — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:106719 | Below 2-yr level | 395.22 m | 7th | -0.006 m/day | 2026-09-29 |

# Awerial County

Lakes | County population about 144,223 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 82 mm below median in the top metre (30-day rain 199% of normal); ~39 mm expected over 2 weeks = 48% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Exposure: County population about 144,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | 8,130 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 1,999 |
| 2 (planning) | 3,109 |
| 3 (severe) | 5,996 |
| Displaced in the planning case | 865 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Bun-agok | 897 | 890 | 4 (4) | 2 (2) | 2,527 (65) | 83.1 (82.5) |
| Nile | 771 | 646 | 5 (5) | 0 (0) | 506 (18) | 0.0 (0.0) |
| Puluk | 728 | 596 | 2 (2) | 2 (2) | 7,474 (200) | 23.4 (21.9) |
| Abuyong | 673 | 569 | 8 (7) | 1 (1) | 770 (22) | 44.8 (41.1) |

Health facilities: 6 in the county, 6 on flood-prone ground | Schools: 27 in the county, 26 on flood-prone ground

## River station: Nile km 4919 (hydroweb:112358)

### River level status

Latest pass 2026-10-14: **Above normal** (percentile 79). Level 424.15 m; seasonal median 424.01 m; anomaly +0.14 m. Record: min 422.75 m, max 424.33 m, average 423.65 m.
Baseline: 5 years, 28 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.24 m; 20 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| hydroweb:201328 | Below normal (percentile 29) on 2026-09-29 | 40 days | 2026-11-08 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| hydroweb:105858 | Below normal (percentile 25) on 2026-09-25 | 14 days | 2026-10-28 |

### Exposure within 25 km of the station

WorldPop population (2020): 24,519, of which 23,625 at risk. Schools: 14 (14 at risk). Health facilities: 2 (2 at risk). Buildings (VIDA): 4,339 (103 at risk). Counties within 25 km: Awerial.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Alel I (Awerial) | 6,232 (6,054) | 286 | 1 (1) | 0 (0) |
| Nile (Awerial) | 5,951 (5,684) | 184 | 4 (4) | 0 (0) |
| Dor (Awerial) | 5,128 (4,926) | 2,601 | 6 (6) | 1 (1) |
| Bun-agok (Awerial) | 2,439 (2,397) | 889 | 1 (1) | 1 (1) |

# Cueibet County

Lakes | County population about 189,199 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 72 mm below median in the top metre (30-day rain 136% of normal); ~31 mm expected over 2 weeks = 42% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Exposure: County population about 189,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 33,000 | 68,988 | 52,395 | 13,655 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 3,076 |
| 2 (planning) | 4,785 |
| 3 (severe) | 9,228 |
| Displaced in the planning case | 1,332 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Malou Pec | 1,650 | 1,622 | 6 (6) | 5 (5) | 14,372 (386) | 190.0 (187.2) |
| Citcok | 1,008 | 1,002 | 12 (12) | 3 (3) | 1,873 (38) | 36.5 (36.4) |
| Abiriu | 620 | 598 | 9 (9) | 5 (5) | 14,184 (310) | 78.0 (75.4) |
| Pagor | 598 | 584 | 4 (4) | 0 (0) | 2,760 (66) | 59.9 (58.3) |

Health facilities: 17 in the county, 17 on flood-prone ground | Schools: 35 in the county, 35 on flood-prone ground

## River level — nearest gauge: Gulnam km 4631

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county's own sub-basin, about 26 km away (high confidence). Altimetry levels are "as seen by satellite" — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:110221 | Stale (last pass 274 d ago) | 412.23 m | 71th | -0.000 m/day | 2026-01-19 |

# Rumbek Centre County

Lakes | County population about 222,497 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 97 mm below median in the top metre (30-day rain 101% of normal); ~30 mm expected over 2 weeks = 31% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Exposure: County population about 222,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | 88,865 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 24,492 |
| 2 (planning) | 38,099 |
| 3 (severe) | 73,477 |
| Displaced in the planning case | 10,602 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Amongpiny | 1,249 | 1,211 | 4 (4) | 1 (1) | 3,460 (93) | 95.3 (92.1) |
| Mayom | 1,008 | 985 | 1 (1) | 0 (0) | 716 (13) | 54.5 (49.9) |
| Matangai | 976 | 953 | 25 (24) | 12 (10) | 37,517 (996) | 76.8 (76.0) |
| Malek 2 | 470 | 470 | 3 (3) | 1 (1) | 214 (11) | 22.9 (22.9) |

Health facilities: 20 in the county, 18 on flood-prone ground | Schools: 38 in the county, 37 on flood-prone ground

## River level — nearest gauge: Gulnam km 4631

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county's own sub-basin, about 0 km away (high confidence). Altimetry levels are "as seen by satellite" — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:110221 | Stale (last pass 274 d ago) | 412.23 m | 71th | -0.000 m/day | 2026-01-19 |

# Rumbek East County

Lakes | County population about 180,970 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 70 mm below median in the top metre (30-day rain 126% of normal); ~33 mm expected over 2 weeks = 48% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Exposure: County population about 181,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 15,000 | not listed | 93,459 | 22,655 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 11,349 |
| 2 (planning) | 17,654 |
| 3 (severe) | 34,047 |
| Displaced in the planning case | 4,913 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Paloc | 1,868 | 1,775 | 1 (1) | 3 (3) | 2,445 (44) | 111.7 (110.1) |
| Cueicok | 409 | 401 | 7 (7) | 4 (4) | 7,762 (222) | 33.7 (32.3) |
| Aduel | 411 | 400 | 9 (9) | 6 (6) | 6,062 (138) | 14.0 (13.9) |
| Atiaba | 292 | 292 | 6 (6) | 3 (3) | 7,802 (191) | 31.0 (30.8) |

Health facilities: 24 in the county, 24 on flood-prone ground | Schools: 42 in the county, 41 on flood-prone ground

## River level — nearest gauge: Gulnam km 4669

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county's own sub-basin, about 0 km away (high confidence). Altimetry levels are "as seen by satellite" — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:104259 | Below 2-yr level | 424.08 m | 0th | -0.006 m/day | 2026-10-04 |

# Rumbek North County

Lakes | County population about 75,047 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 103 mm below median in the top metre (30-day rain 87% of normal); ~22 mm expected over 2 weeks = 21% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Exposure: County population about 75,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 12,000 | not listed | not listed | 45,225 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 11,215 |
| 2 (planning) | 17,445 |
| 3 (severe) | 33,644 |
| Displaced in the planning case | 4,854 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Mayen | 2,575 | 2,556 | 7 (7) | 2 (2) | 1,068 (26) | 102.1 (101.5) |
| Malueeth | 983 | 978 | 4 (4) | 2 (2) | 1,945 (50) | 34.5 (34.5) |
| Madol | 385 | 385 | 1 (1) | 0 (0) | 205 (4) | 0.0 (0.0) |
| Aloor | 71 | 71 | 0 (0) | 1 (1) | 652 (16) | 0.0 (0.0) |

Health facilities: 9 in the county, 9 on flood-prone ground | Schools: 25 in the county, 25 on flood-prone ground

## River level — nearest gauge: Gulnam km 4574

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county’s own sub-basin, about 0 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:104260 | Below 2-yr level | 397.46 m | 0th | -0.002 m/day | 2026-10-04 |

# Wulu County

Lakes | County population about 92,247 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 52 mm below median in the top metre (30-day rain 128% of normal); ~49 mm expected over 2 weeks = 94% of the deficit. Soils should recover if the rain arrives
• Exposure: About 0 people live on ground that has flooded before (of ~92,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | 5,570 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 1,319 |
| 2 (planning) | 2,052 |
| 3 (severe) | 3,957 |
| Displaced in the planning case | 571 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Bargel | 5,628 | 4,680 | 7 (7) | 4 (4) | 3,588 (75) | 282.1 (240.4) |
| Domoloto | 5,329 | 4,609 | 1 (1) | 4 (3) | 4,247 (74) | 224.7 (205.8) |
| Wulu | 724 | 639 | 3 (3) | 5 (5) | 7,431 (126) | 69.5 (65.5) |
| Makundi | 162 | 149 | 0 (0) | 1 (1) | 417 (9) | 12.3 (12.1) |

Health facilities: 14 in the county, 13 on flood-prone ground | Schools: 11 in the county, 11 on flood-prone ground

## River level — nearest gauge: Unknown, River

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county’s own sub-basin, about 7 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| dahiti:2686 | Below 2-yr level | 474.92 m | 0th | -0.016 m/day | 2026-09-11 |

# Yirol East County

Lakes | County population about 165,810 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 42 mm below median in the top metre (30-day rain 156% of normal); ~34 mm expected over 2 weeks = 81% of the deficit. Soils should recover if the rain arrives
• Exposure: About 4,000 people live on ground that has flooded before (of ~166,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 1,398 | not listed | not listed | 26,155 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 11,537 |
| 2 (planning) | 17,946 |
| 3 (severe) | 34,610 |
| Displaced in the planning case | 4,994 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Malek | 2,040 | 1,909 | 11 (11) | 1 (1) | 3,348 (92) | 109.3 (104.4) |
| Adior | 1,673 | 1,398 | 12 (12) | 3 (2) | 3,932 (110) | 93.7 (86.0) |
| Tinagau | 805 | 799 | 2 (2) | 1 (1) | 1,909 (33) | 60.4 (60.0) |
| Pagarau | 700 | 615 | 1 (1) | 1 (1) | 2,672 (83) | 77.0 (66.6) |

Health facilities: 9 in the county, 8 on flood-prone ground | Schools: 35 in the county, 35 on flood-prone ground

## River station: White Nile km 4568 (hydroweb:7883)

### River level status

Latest pass 2026-10-08: **Near normal** (percentile 61). Level 411.86 m; seasonal median 411.81 m; anomaly +0.05 m. Record: min 410.92 m, max 412.39 m, average 411.67 m.

Baseline: 10 years, 22 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.07 m; 27 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| hydroweb:7960 | Above normal (percentile 85) on 2026-10-14 | 30 days | 2026-11-13 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| hydroweb:7887 | Below normal (percentile 22) on 2026-09-23 | 16 days | 2026-10-24 |

### Exposure within 25 km of the station

WorldPop population (2020): 24,161, of which 15,847 at risk. Schools: 10 (10 at risk). Health facilities: 1 (0 at risk). Buildings (VIDA): 407 (9 at risk). Counties within 25 km: Panyijiar, Twic East, Yirol East.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Adior (Yirol East) | 11,999 (9,187) | 265 | 10 (10) | 1 (0) |
| Ajuong (Twic East) | 11,088 (5,588) | 133 | 0 (0) | 0 (0) |
| Tinagau (Yirol East) | 1,074 (1,072) | 9 | 0 (0) | 0 (0) |
| Pachienjok (Panyijiar) | 0 (0) | 0 | 0 (0) | 0 (0) |

# Yirol West County

Lakes | County population about 181,325 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 92 mm below median in the top metre (30-day rain 166% of normal); ~37 mm expected over 2 weeks = 40% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Exposure: County population about 181,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | 87,830 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 22,730 |
| 2 (planning) | 35,358 |
| 3 (severe) | 68,191 |
| Displaced in the planning case | 9,839 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Geng-geng | 1,881 | 1,844 | 7 (7) | 1 (1) | 2,667 (52) | 47.2 (46.7) |
| Anuol | 1,023 | 999 | 0 (0) | 3 (3) | 2,900 (57) | 72.9 (71.3) |
| Gher | 662 | 655 | 3 (3) | 1 (1) | 2,063 (44) | 27.4 (27.2) |
| Yirol | 654 | 648 | 3 (3) | 3 (3) | 11,496 (373) | 22.6 (22.1) |

Health facilities: 14 in the county, 14 on flood-prone ground | Schools: 27 in the county, 27 on flood-prone ground

## River level — nearest gauge: Yei km 4546

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county’s own sub-basin, about 44 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:104992 | Below 2-yr level | 412.83 m | 7th | +0.000 m/day | 2026-09-21 |

# Aweil Centre County

Northern Bahr el Ghazal | County population about 78,958 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 64 mm below median in the top metre (30-day rain 126% of normal); ~13 mm expected over 2 weeks = 20% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell possible (46%) on dry soils: monitor crops and pasture
• Exposure: County population about 79,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 1,800 | 45,288 | 48,864 | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 364 |
| 2 (planning) | 566 |
| 3 (severe) | 1,092 |
| Displaced in the planning case | 157 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Achana | 3,401 | 2,249 | 1 (0) | 2 (1) | 635 (9) | 126.7 (90.6) |
| Abul | 2,893 | 1,402 | 6 (1) | 2 (0) | 1,003 (12) | 145.5 (68.5) |
| Nyalath | 1,747 | 1,281 | 15 (11) | 2 (2) | 2,177 (32) | 65.4 (44.7) |
| Aroyo | 1,166 | 866 | 6 (6) | 1 (1) | 842 (18) | 103.5 (76.0) |

Health facilities: 15 in the county, 10 on flood-prone ground | Schools: 60 in the county, 36 on flood-prone ground

## River level — nearest gauge: Chel km 4862

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county's own sub-basin, about 0 km away (high confidence). Altimetry levels are "as seen by satellite" — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:101700 | Below 2-yr level | 447.46 m | 0th | +0.018 m/day | 2026-10-17 |

# Aweil East County

Northern Bahr el Ghazal | County population about 395,769 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 58 mm below median in the top metre (30-day rain 178% of normal); ~5 mm expected over 2 weeks = 8% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (82%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 396,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 40,000 | 135,030 | 91,128 | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 1,639 |
| 2 (planning) | 2,549 |
| 3 (severe) | 4,916 |
| Displaced in the planning case | 709 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Malual-bai | 1,753 | 1,144 | 23 (13) | 13 (8) | 21,540 (481) | 45.5 (22.6) |
| Baach | 1,422 | 1,022 | 8 (6) | 11 (7) | 38,740 (930) | 68.0 (49.9) |
| Madhol | 995 | 577 | 29 (20) | 6 (4) | 19,359 (515) | 49.7 (29.1) |
| Wunlang | 584 | 396 | 10 (5) | 4 (4) | 19,311 (509) | 13.5 (9.6) |

Health facilities: 53 in the county, 35 on flood-prone ground | Schools: 108 in the county, 60 on flood-prone ground

## Reported news

• 03 Oct: **Hepatitis E (water):** State health officials, including the Ministry of Health's health education focal point Luka Lual Aliue, report 40 hepatitis E cases, no deaths so far, in epidemiological weeks 38 and 39 in Northern Bahr el Ghazal (counties including Aweil East, Aweil North, Gok Machar and Aweil West); health officials link the surge to water sources contaminated during the rainy season. (Eye Radio)

From local media and ReliefWeb; single-source items are unverified. Counties are as named in the article, or inferred from the place where stated.

## River level — nearest gauge: Lol km 4620

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 0 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:203695 | Below 2-yr level | 412.13 m | 0th | +0.010 m/day | 2026-10-15 |

# Aweil North County

Northern Bahr el Ghazal | County population about 185,929 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 64 mm below median in the top metre (30-day rain 108% of normal); ~3 mm expected over 2 weeks = 5% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (86%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 186,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 14,041 | 30,846 | 16,820 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 3,727 |
| 2 (planning) | 5,797 |
| 3 (severe) | 11,180 |
| Displaced in the planning case | 1,613 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Malual West | 3,399 | 2,740 | 11 (9) | 9 (5) | 9,390 (181) | 3.6 (3.5) |
| Malual East | 1,055 | 647 | 19 (11) | 9 (4) | 26,721 (601) | 15.0 (13.4) |
| Malual Centre | 753 | 449 | 9 (3) | 7 (2) | 16,761 (362) | 3.2 (1.2) |
| Malual North | 819 | 441 | 15 (4) | 4 (2) | 26,298 (470) | 48.3 (26.9) |

Health facilities: 37 in the county, 19 on flood-prone ground | Schools: 66 in the county, 33 on flood-prone ground

## Reported news

• 03 Oct: **Hepatitis E (water):** State health officials, including the Ministry of Health's health education focal point Luka Lual Aliue, report 40 hepatitis E cases, no deaths so far, in epidemiological weeks 38 and 39 in Northern Bahr el Ghazal (counties including Aweil East, Aweil North, Gok Machar and Aweil West); health officials link the surge to water sources contaminated during the rainy season. (Eye Radio)

From local media and ReliefWeb; single-source items are unverified. Counties are as named in the article, or inferred from the place where stated.

## River level — nearest gauge: Lol km 4838

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 0 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:7906 | Below 2-yr level | 448.77 m | 0th | -0.024 m/day | 2026-09-22 |

# Aweil South County

Northern Bahr el Ghazal | County population about 151,604 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 55 mm below median in the top metre (30-day rain 136% of normal); ~9 mm expected over 2 weeks = 16% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell possible (46%) on dry soils: monitor crops and pasture
• Exposure: County population about 152,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 23,000 | 45,246 | 85,302 | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 571 |
| 2 (planning) | 888 |
| 3 (severe) | 1,713 |
| Displaced in the planning case | 247 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Tar-weng | 454 | 389 | 6 (5) | 2 (0) | 4,148 (124) | 22.3 (17.8) |
| Gakrol | 267 | 233 | 5 (4) | 5 (3) | 4,186 (94) | 41.4 (36.4) |
| Tiar-aleit | 347 | 231 | 6 (6) | 3 (2) | 7,840 (230) | 30.9 (24.6) |
| Wathmuok | 222 | 190 | 6 (3) | 3 (1) | 3,744 (89) | 12.4 (11.5) |

Health facilities: 21 in the county, 12 on flood-prone ground | Schools: 37 in the county, 26 on flood-prone ground

## River level — nearest gauge: Bahr km 4651

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county's own sub-basin, about 0 km away (high confidence). Altimetry levels are "as seen by satellite" — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:7813 | Below 2-yr level | 421.50 m | 0th | -0.002 m/day | 2026-09-26 |

# Aweil West County

Northern Bahr el Ghazal | County population about 223,173 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 66 mm below median in the top metre (30-day rain 110% of normal); ~6 mm expected over 2 weeks = 10% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (70%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 223,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 12,158 | 30,168 | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 864 |
| 2 (planning) | 1,344 |
| 3 (severe) | 2,592 |
| Displaced in the planning case | 374 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Achana 2 | 1,619 | 1,514 | 0 (0) | 3 (3) | 862 (17) | 63.5 (59.7) |
| Mariem West | 889 | 677 | 3 (1) | 3 (2) | 12,251 (211) | 18.8 (16.6) |
| Ayat West | 501 | 432 | 4 (4) | 6 (5) | 2,581 (59) | 21.6 (20.1) |
| Ayat Centre | 407 | 338 | 3 (3) | 5 (3) | 4,691 (101) | 16.8 (14.9) |

Health facilities: 45 in the county, 22 on flood-prone ground | Schools: 44 in the county, 19 on flood-prone ground

## Reported news

• 03 Oct: **Hepatitis E (water):** State health officials, including the Ministry of Health's health education focal point Luka Lual Aliue, report 40 hepatitis E cases, no deaths so far, in epidemiological weeks 38 and 39 in Northern Bahr el Ghazal (counties including Aweil East, Aweil North, Gok Machar and Aweil West); health officials link the surge to water sources contaminated during the rainy season. (Eye Radio)

From local media and ReliefWeb; single-source items are unverified. Counties are as named in the article, or inferred from the place where stated.

## River level — nearest gauge: Wadi Boro, River

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county's own sub-basin, about 0 km away (high confidence). Altimetry levels are "as seen by satellite" — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| dahiti:23343 | Below 2-yr level | 454.21 m | 0th | -0.010 m/day | 2026-09-03 |

# Abiemnhom County

Unity | County population about 60,349 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 69 mm below median in the top metre (30-day rain 91% of normal); ~4 mm expected over 2 weeks = 6% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (74%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 60,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 1,367 |
| 2 (planning) | 2,127 |
| 3 (severe) | 4,102 |
| Displaced in the planning case | 592 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Aworpiny | 696 | 649 | 0 (0) | 0 (0) | 11 (0) | 12.8 (12.7) |
| Panyang 2 | 613 | 422 | 0 (0) | 0 (0) | 249 (3) | 43.6 (25.2) |
| Abiemnhom | 416 | 406 | 4 (4) | 8 (8) | 4,649 (109) | 47.9 (46.8) |
| Manjonga | 682 | 322 | 0 (0) | 0 (0) | 142 (1) | 15.2 (12.6) |

Health facilities: 8 in the county, 8 on flood-prone ground | Schools: 4 in the county, 4 on flood-prone ground

## River level — nearest gauge: Bhar-al-arab, River

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: upstream of the county, about 0 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| dahiti:18741 | Below 2-yr level | 394.04 m | 18th | -0.003 m/day | 2026-09-01 |

# Guit County

Unity | County population about 73,878 | Issued 21 October 2026

## Advisory

- No significant change expected: near normal soils, about 4 mm of rain in week 1
- Exposure: About 3,000 people live on ground that has flooded before (of ~74,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 8,000 | not listed | 5,010 | 3,336 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 3,888 |
| 2 (planning) | 6,048 |
| 3 (severe) | 11,664 |
| Displaced in the planning case | 1,683 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Settlements assessed Sept 2025

| Payam | Settlements | People | Flooded | High ground | Small towns |
|---|---|---|---|---|---|
| Guit | 1 | 5,600 | 5,600 | 0 | 0 |
| Kedad | 3 | 3,700 | 3,700 | 0 | 0 |
| Kuach | 9 | 18,500 | 2,800 | 14,200 | 1,500 |
| Kuerguini | 7 | 20,040 | 8,170 | 11,870 | 0 |
| Niemni | 5 | 13,700 | 7,900 | 0 | 5,800 |
| Nyathoar | 3 | 3,650 | 3,650 | 0 | 0 |
| Wathnyona | 3 | 8,800 | 7,800 | 1,000 | 0 |
| **Guit County** | **31** | **73,990** | **39,620** | **27,070** | **7,300** |

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Kedad | 1,026 | 971 | 11 (11) | 2 (2) | 1,298 (32) | 31.5 (30.8) |
| Kuach | 780 | 734 | 4 (4) | 4 (4) | 811 (28) | 7.0 (7.0) |
| Niemni | 855 | 718 | 2 (0) | 2 (2) | 638 (33) | 28.2 (27.7) |
| Wathnyona | 317 | 282 | 0 (0) | 2 (2) | 500 (11) | 40.2 (34.9) |

Health facilities: 12 in the county, 12 on flood-prone ground | Schools: 21 in the county, 19 on flood-prone ground

## River station: White Nile km 4152 (hydroweb:7881)

### River level status

Latest pass 2026-10-08: **Unusually high** (percentile 93). Level 392.55 m; seasonal median 392.27 m; anomaly +0.28 m. Record: min 392.02 m, max 392.58 m, average 392.28 m.

Baseline: 10 years, 22 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.01 m; 27 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| hydroweb:7882 | Above normal (percentile 88) on 2026-10-08 | 4 days | 2026-10-12 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| hydroweb:7888 | Near normal (percentile 50) on 2026-09-25 | 6 days | 2026-10-14 |

### Exposure within 25 km of the station

WorldPop population (2020): 20,293, of which 16,361 at risk. Schools: 3 (1 at risk). Health facilities: 1 (1 at risk). Buildings (VIDA): 290 (2 at risk). Counties within 25 km: Fangak, Guit, Pariang.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Paguir (Fangak) | 9,609 (8,677) | 60 | 0 (0) | 1 (1) |
| Niemni (Guit) | 5,075 (4,152) | 69 | 2 (0) | 0 (0) |
| Biu (Pariang) | 3,136 (1,199) | 63 | 0 (0) | 0 (0) |
| Kedad (Guit) | 2,473 (2,333) | 98 | 1 (1) | 0 (0) |

# Koch County

Unity | County population about 115,158 | Issued 21 October 2026

## Advisory

- No significant change expected: near normal soils, about 7 mm of rain in week 1
- Exposure: About 1,000 people live on ground that has flooded before (of ~115,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 2,898 | not listed | 36,278 | 47,984 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 12,999 |
| 2 (planning) | 20,221 |
| 3 (severe) | 38,998 |
| Displaced in the planning case | 5,627 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Settlements assessed Sept 2025

| Payam | Settlements | People | Flooded | High ground | Small towns |
|---|---|---|---|---|---|
| Boaw | 2 | 15,197 | 15,197 | 0 | 0 |
| Gany | 2 | 7,681 | 0 | 7,681 | 0 |
| Jaak | 8 | 33,479 | 19,047 | 14,432 | 0 |
| Kuachlual | 1 | 12,382 | 12,382 | 0 | 0 |
| Ngony | 3 | 18,886 | 3,900 | 14,986 | 0 |
| Norbor | 1 | 4,700 | 0 | 4,700 | 0 |
| Pakur | 1 | 3,680 | 0 | 3,680 | 0 |
| **Koch County** | **18** | **96,005** | **50,526** | **45,479** | **0** |

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Pakur | 1,105 | 940 | 4 (3) | 2 (2) | 25 (0) | 0.0 (0.0) |
| Jaak | 984 | 921 | 3 (3) | 2 (2) | 3,125 (110) | 2.1 (2.1) |
| Boaw | 791 | 776 | 6 (6) | 1 (1) | 856 (22) | 30.1 (30.1) |
| Norbor | 531 | 521 | 0 (0) | 1 (1) | 85 (3) | 3.1 (2.9) |

Health facilities: 10 in the county, 10 on flood-prone ground | Schools: 26 in the county, 25 on flood-prone ground

## River level — nearest gauge: Bhr Lgzl Trib 03 km 4333

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: upstream of the county, about 0 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:111298 | Below 2-yr level | 392.96 m | 10th | +0.000 m/day | 2026-10-11 |

# Leer County

Unity | County population about 86,784 | Issued 21 October 2026

## Advisory

- No significant change expected: near normal soils, about 12 mm of rain in week 1
- Exposure: About 1,000 people live on ground that has flooded before (of ~87,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 41,000 | 48,295 | 6,611 | 62,796 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 14,888 |
| 2 (planning) | 23,159 |
| 3 (severe) | 44,664 |
| Displaced in the planning case | 6,444 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Settlements assessed Sept 2025

| Payam | Settlements | People | Flooded | High ground | Small towns |
|---|---|---|---|---|---|
| Adok | 6 | 15,600 | 5,000 | 10,600 | 0 |
| Bou | 1 | 1,400 | 1,400 | 0 | 0 |
| Guat | 1 | 4,400 | 0 | 4,400 | 0 |
| Juong Kang | 2 | 20,000 | 100 | 19,900 | 0 |
| Leer | 2 | 12,900 | 0 | 12,900 | 0 |
| Padeah | 3 | 2,900 | 0 | 2,900 | 0 |
| Pilieny | 3 | 13,100 | 2,800 | 10,300 | 0 |
| Yang | 3 | 9,400 | 0 | 9,400 | 0 |
| **Leer County** | **21** | **79,700** | **9,300** | **70,400** | **0** |

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Yang | 632 | 487 | 2 (2) | 1 (1) | 2,040 (52) | 21.0 (20.9) |
| Pilieny | 355 | 353 | 0 (0) | 1 (1) | 872 (19) | 29.3 (29.2) |
| Padeah | 220 | 202 | 3 (3) | 2 (2) | 1,349 (33) | 0.0 (0.0) |
| Adok | 223 | 183 | 10 (10) | 2 (2) | 3,952 (99) | 7.8 (7.2) |

Health facilities: 14 in the county, 14 on flood-prone ground | Schools: 22 in the county, 22 on flood-prone ground

## River station: White Nile km 4371 (hydroweb:7875)

### River level status

Latest pass 2026-10-14: **Below normal** (percentile 33). Level 400.67 m; seasonal median 400.71 m; anomaly -0.04 m. Record: min 400.22 m, max 401.00 m, average 400.65 m.

Baseline: 10 years, 61 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.01 m; 10 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| hydroweb:7884 | Unusually low (percentile 0) on 2026-10-06 | 0 days | 2026-10-06 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| hydroweb:7874 | Above normal (percentile 89) on 2026-10-14 | 3 days | 2026-10-17 |

### Exposure within 25 km of the station

WorldPop population (2020): 46,458, of which 31,550 at risk. Schools: 3 (3 at risk). Health facilities: 2 (2 at risk). Buildings (VIDA): 2,855 (80 at risk). Counties within 25 km: Ayod, Leer, Panyijiar.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Yang (Leer) | 20,027 (14,969) | 1,891 | 1 (1) | 1 (1) |
| Wau (Ayod) | 9,715 (6,467) | 37 | 0 (0) | 0 (0) |
| Adok (Leer) | 5,788 (4,004) | 886 | 2 (2) | 1 (1) |
| Pajiek (Ayod) | 5,038 (1,179) | 11 | 0 (0) | 0 (0) |

# Mayendit County

Unity | County population about 74,335 | Issued 21 October 2026

## Advisory

• No significant change expected: near normal soils, about 11 mm of rain in week 1
• Exposure: About 2,000 people live on ground that has flooded before (of ~74,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 31,000 | 17,004 | 23,963 | 58,438 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 13,551 |
| 2 (planning) | 21,080 |
| 3 (severe) | 40,654 |
| Displaced in the planning case | 5,866 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Settlements assessed Sept 2025

| Payam | Settlements | People | Flooded | High ground | Small towns |
|---|---|---|---|---|---|
| Bor 2 | 2 | 4,700 | 0 | 4,700 | 0 |
| Dablual | 5 | 13,300 | 7,000 | 6,300 | 0 |
| Rubkuay | 9 | 25,700 | 0 | 25,700 | 0 |
| Tutnyang | 4 | 11,800 | 2,500 | 9,300 | 0 |
| **Mayendit County** | **20** | **55,500** | **9,500** | **46,000** | **0** |

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Pabuong | 1,196 | 1,192 | 0 (0) | 2 (2) | 148 (0) | 0.2 (0.2) |
| Tharjiath | 563 | 550 | 1 (1) | 0 (0) | 19 (0) | 0.0 (0.0) |
| Maal | 465 | 461 | 4 (4) | 2 (2) | 794 (24) | 34.8 (34.0) |
| Bor 2 | 288 | 285 | 2 (2) | 2 (2) | 611 (27) | 20.3 (20.1) |

Health facilities: 15 in the county, 15 on flood-prone ground | Schools: 29 in the county, 29 on flood-prone ground

## River level — nearest gauge: Bahr Al Arab Trib 02 km 4435

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county's own sub-basin, about 2 km away (high confidence). Altimetry levels are "as seen by satellite" — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:104261 | Below 2-yr level | 394.37 m | 35th | +0.001 m/day | 2026-10-04 |

# Mayom County

Unity | County population about 170,251 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 98 mm below median in the top metre (30-day rain 60% of normal); ~8 mm expected over 2 weeks = 8% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (60%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 170,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 60,000 | not listed | 42,844 | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 7,471 |
| 2 (planning) | 11,622 |
| 3 (severe) | 22,414 |
| Displaced in the planning case | 3,234 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Wangkei | 774 | 730 | 0 (0) | 1 (1) | 6,111 (181) | 49.7 (48.5) |
| Kuerbuone | 770 | 700 | 2 (2) | 1 (1) | 5,111 (160) | 25.3 (24.6) |
| Riak | 901 | 681 | 0 (0) | 1 (1) | 5,652 (160) | 5.2 (5.2) |
| Pup | 683 | 646 | 0 (0) | 1 (1) | 1,702 (48) | 15.4 (14.9) |

Health facilities: 10 in the county, 10 on flood-prone ground | Schools: 5 in the county, 5 on flood-prone ground

## River station: Jur, River (dahiti:2688)

### River level status

Latest pass 2026-09-11: **Near normal** (percentile 65). Level 392.62 m; seasonal median 392.51 m; anomaly +0.11 m. Record: min 391.63 m, max 392.77 m, average 392.37 m.

Baseline: 10 years, 51 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.00 m; 10 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| dahiti:2687 | Above normal (percentile 88) on 2026-09-11 | 4 days | 2026-09-15 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| dahiti:23338 | Above normal (percentile 78) on 2026-09-05 | 5 days | 2026-09-16 |

### Exposure within 25 km of the station

WorldPop population (2020): 37,127, of which 27,192 at risk. Schools: 1 (0 at risk). Health facilities: 1 (1 at risk). Buildings (VIDA): 4,944 (138 at risk). Counties within 25 km: Koch, Mayom, Rubkona, Tonj North.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Riak (Mayom) | 16,351 (11,278) | 2,862 | 0 (0) | 1 (1) |
| Pakur (Koch) | 6,488 (4,463) | 10 | 1 (0) | 0 (0) |
| Wangkei (Mayom) | 4,515 (4,002) | 1,505 | 0 (0) | 0 (0) |
| Kuerbuone (Mayom) | 3,362 (2,353) | 290 | 0 (0) | 0 (0) |

# Panyijiar County

Unity | County population about 126,239 | Issued 21 October 2026

## Advisory

- No significant change expected: dry soils, about 13 mm of rain in week 1
- Exposure: About 4,000 people live on ground that has flooded before (of ~126,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 44,836 | 6,420 | 56,318 | 82,548 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 20,175 |
| 2 (planning) | 31,383 |
| 3 (severe) | 60,524 |
| Displaced in the planning case | 8,733 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Settlements assessed Sept 2025

| Payam | Settlements | People | Flooded | High ground | Small towns |
|---|---|---|---|---|---|
| Ganyliel | 2 | 4,100 | 2,300 | 1,800 | 0 |
| Kol | 2 | 27,600 | 27,600 | 0 | 0 |
| Mayom 2 | 1 | 4,800 | 4,800 | 0 | 0 |
| Nyal | 5 | 22,100 | 3,200 | 15,000 | 3,900 |
| Pachaar | 3 | 7,900 | 1,200 | 2,600 | 4,100 |
| Pachak | 3 | 14,300 | 10,100 | 4,200 | 0 |
| Pachienjok | 3 | 8,900 | 5,700 | 3,200 | 0 |
| Panyijiar | 1 | 1,800 | 0 | 1,800 | 0 |
| Thoarnhoum | 2 | 9,700 | 2,200 | 0 | 7,500 |
| Tiap | 1 | 6,100 | 6,100 | 0 | 0 |
| **Panyijiar County** | **23** | **107,300** | **63,200** | **28,600** | **15,500** |

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Nyal | 1,314 | 984 | 6 (5) | 4 (4) | 5,885 (158) | 52.1 (33.4) |
| Mayom 2 | 625 | 607 | 2 (2) | 3 (3) | 495 (14) | 42.5 (38.5) |
| Panyijiar | 513 | 509 | 2 (2) | 2 (2) | 984 (29) | 37.4 (37.4) |
| Pachak | 612 | 468 | 1 (1) | 1 (1) | 1,551 (40) | 64.8 (57.1) |

Health facilities: 25 in the county, 25 on flood-prone ground | Schools: 36 in the county, 35 on flood-prone ground

## River station: White Nile km 4515 (hydroweb:7878)

### River level status

Latest pass 2026-10-14: **Above normal** (percentile 83). Level 408.86 m; seasonal median 408.66 m; anomaly +0.20 m. Record: min 407.71 m, max 409.07 m, average 408.54 m.

Baseline: 10 years, 61 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.08 m; 10 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| hydroweb:7879 | Near normal (percentile 50) on 2026-10-14 | 2 days | 2026-10-16 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| hydroweb:7877 | Below normal (percentile 26) on 2026-10-14 | 6 days | 2026-10-20 |

### Exposure within 25 km of the station

WorldPop population (2020): 21,871, of which 11,467 at risk. Schools: 5 (5 at risk). Health facilities: 4 (4 at risk). Buildings (VIDA): 3,344 (97 at risk). Counties within 25 km: Duk, Panyijiar, Twic East, Yirol East.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Dongchak (Duk) | 7,267 (2,694) | 177 | 0 (0) | 0 (0) |
| Pachienjok (Panyijiar) | 5,097 (3,616) | 851 | 3 (3) | 2 (2) |
| Ajuong (Twic East) | 3,935 (1,120) | 39 | 0 (0) | 0 (0) |
| Adior (Yirol East) | 1,874 (1,370) | 12 | 0 (0) | 0 (0) |

# Pariang County

Unity | County population about 143,832 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 71 mm below median in the top metre (30-day rain 99% of normal); ~3 mm expected over 2 weeks = 5% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (90%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 144,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 3,124 |
| 2 (planning) | 4,860 |
| 3 (severe) | 9,373 |
| Displaced in the planning case | 1,352 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Jamjang | 1,874 | 694 | 5 (1) | 8 (1) | 22,683 (140) | 100.8 (49.5) |
| Werthen | 1,302 | 520 | 0 (0) | 5 (1) | 22,039 (257) | 76.2 (32.0) |
| Wunkur | 1,290 | 516 | 0 (0) | 0 (0) | 57 (0) | 38.9 (11.2) |
| Biu | 1,685 | 515 | 3 (0) | 3 (0) | 1,858 (18) | 79.7 (20.1) |

Health facilities: 23 in the county, 4 on flood-prone ground | Schools: 17 in the county, 4 on flood-prone ground

## River station: Bhar El Gazal km 4147 (hydroweb:7826)

### River level status

Latest pass 2026-10-08: **Unusually high** (percentile 100). Level 391.40 m; seasonal median 391.13 m; anomaly +0.27 m. Record: min 390.95 m, max 391.49 m, average 391.18 m.

Baseline: 6 years, 11 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.05 m; 27 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| hydroweb:7829 | Below normal (percentile 31) on 2026-10-16 | 10 days | 2026-10-26 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| hydroweb:7828 | Near normal (percentile 56) on 2026-09-21 | 32 days | 2026-11-09 |

### Exposure within 25 km of the station

WorldPop population (2020): 18,085, of which 11,142 at risk. Schools: 5 (0 at risk). Health facilities: 1 (0 at risk). Buildings (VIDA): 725 (7 at risk). Counties within 25 km: Fangak, Guit, Pariang.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Biu (Pariang) | 7,022 (2,300) | 499 | 3 (0) | 1 (0) |
| Niemni (Guit) | 5,425 (4,354) | 75 | 2 (0) | 0 (0) |
| Paguir (Fangak) | 5,091 (4,116) | 21 | 0 (0) | 0 (0) |
| Kedad (Guit) | 352 (335) | 0 | 0 (0) | 0 (0) |

# Rubkona County

Unity | County population about 361,802 | Issued 21 October 2026

## Advisory

• Dry spell likely (70%): suitable for weeding, harvesting and drying; delay planting
• Exposure: About 16,000 people live on ground that has flooded before (of ~362,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 32,648 | 52,247 | 28,000 | 1,000 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 28,002 |
| 2 (planning) | 43,558 |
| 3 (severe) | 84,005 |
| Displaced in the planning case | 12,121 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Budaang | 1,461 | 1,152 | 3 (2) | 1 (1) | 3,981 (105) | 51.0 (47.7) |
| Nhialdiu | 576 | 561 | 11 (11) | 4 (4) | 5,199 (163) | 0.0 (0.0) |
| Rubkotne | 576 | 534 | 14 (14) | 13 (8) | 25,082 (729) | 12.2 (10.8) |
| Panhiany | 409 | 406 | 6 (6) | 0 (0) | 996 (29) | 25.8 (25.6) |

Health facilities: 23 in the county, 17 on flood-prone ground | Schools: 65 in the county, 59 on flood-prone ground

## Reported news

• 05 Oct: **Flood:** Flooding has submerged about 70% of the land in Bentiu, and the dykes built and maintained around the clock by UNMISS and IOM protect about 300,000 people. UNMISS's Bentiu field office head says 50,000 people would be submerged if UN and IOM work were affected and a dyke breach were not repaired within ten hours, and that IOM faces a shortage of resources for dyke maintenance and pumping; he expects heavy rain with El Nino from October to February (county inferred from Bentiu). (Radio Yei (UNMISS))

From local media and ReliefWeb; single-source items are unverified. Counties are as named in the article, or inferred from the place where stated.

## River station: Bahr Al Arab km 4263 (hydroweb:111300)

### River level status

Latest pass 2026-10-11: **Near normal** (percentile 38). Level 391.54 m; seasonal median 391.81 m; anomaly -0.27 m. Record: min 390.90 m, max 392.29 m, average 391.66 m.

Baseline: 5 years, 29 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.01 m; 10 days since previous pass.

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| hydroweb:104262 | Unusually low (percentile 10) on 2026-10-04 | 1 days | 2026-10-12 |

### Exposure within 25 km of the station

WorldPop population (2020): 86,184, of which 74,523 at risk. Schools: 15 (14 at risk). Health facilities: 15 (10 at risk). Buildings (VIDA): 27,414 (779 at risk). Counties within 25 km: Guit, Mayom, Pariang, Rubkona.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Budaang (Rubkona) | 39,146 (32,460) | 1,650 | 1 (0) | 1 (1) |
| Rubkotne (Rubkona) | 28,004 (25,347) | 23,950 | 11 (11) | 12 (7) |
| Dhorbor (Rubkona) | 13,958 (13,637) | 1,052 | 1 (1) | 1 (1) |
| Nyeel (Pariang) | 2,288 (344) | 5 | 0 (0) | 0 (0) |

# Baliet County

Upper Nile | County population about 76,145 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 64 mm below median in the top metre (30-day rain 112% of normal); ~6 mm expected over 2 weeks = 10% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (82%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 76,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 13,152 | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 1,960 |
| 2 (planning) | 3,049 |
| 3 (severe) | 5,880 |
| Displaced in the planning case | 848 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Akotweng | 7,822 | 4,956 | 0 (0) | 1 (0) | 2,135 (34) | 156.1 (64.0) |
| Abwong | 1,014 | 728 | 0 (0) | 0 (0) | 77 (3) | 72.5 (54.4) |
| Nyongrial | 682 | 266 | 0 (0) | 1 (0) | 502 (3) | 38.9 (9.3) |
| Akoka | 1,255 | 236 | 2 (0) | 2 (0) | 438 (2) | 87.3 (10.1) |

Health facilities: 12 in the county, 2 on flood-prone ground | Schools: 15 in the county, 2 on flood-prone ground

## River station: Sobat km 4133 (hydroweb:7814)

### River level status

Latest pass 2026-10-14: **Near normal** (percentile 33). Level 394.09 m; seasonal median 394.18 m; anomaly -0.09 m. Record: min 388.74 m, max 394.85 m, average 392.79 m.

Baseline: 10 years, 60 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.01 m; 10 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| hydroweb:7952 | Unusually low (percentile 5) on 2026-10-14 | 0 days | 2026-10-14 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| hydroweb:7953 | Below normal (percentile 25) on 2026-10-16 | 1 days | 2026-10-15 |

### Exposure within 25 km of the station

WorldPop population (2020): 27,925, of which 16,286 at risk. Schools: 4 (1 at risk). Health facilities: 2 (2 at risk). Buildings (VIDA): 2,821 (59 at risk). Counties within 25 km: Baliet, Nyirol, Ulang.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Chuil (Nyirol) | 7,898 (6,267) | 1,464 | 0 (0) | 0 (0) |
| Doma (Ulang) | 7,629 (4,996) | 114 | 0 (0) | 0 (0) |
| Akotweng (Baliet) | 4,482 (2,369) | 289 | 0 (0) | 0 (0) |
| Gel Achiel (Baliet) | 3,806 (1,571) | 751 | 1 (1) | 1 (1) |

# Fashoda County

Upper Nile | County population about 83,775 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 53 mm below median in the top metre (30-day rain 131% of normal); ~1 mm expected over 2 weeks = 3% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (94%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 84,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 13,476 | not listed | 2,620 | 8,690 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 4,020 |
| 2 (planning) | 6,254 |
| 3 (severe) | 12,061 |
| Displaced in the planning case | 1,740 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Lul | 1,795 | 566 | 2 (0) | 4 (1) | 3,752 (20) | 107.4 (33.8) |
| Kodok | 1,455 | 340 | 1 (0) | 8 (0) | 2,762 (19) | 177.4 (41.1) |
| Dethok | 335 | 104 | 1 (0) | 4 (1) | 1,263 (2) | 29.7 (6.8) |
| Kodok Town | 11 | 5 | 0 (0) | 1 (0) | 2,675 (12) | 5.1 (1.0) |

Health facilities: 17 in the county, 2 on flood-prone ground | Schools: 4 in the county, 0 on flood-prone ground

## River station: White Nile km 3905 (hydroweb:7969)

### River level status

Latest pass 2026-10-16: **Near normal** (percentile 59). Level 388.67 m; seasonal median 388.12 m; anomaly +0.55 m. Record: min 385.59 m, max 389.30 m, average 387.64 m.

Baseline: 10 years, 22 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.03 m; 27 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| hydroweb:7964 | Near normal (percentile 59) on 2026-10-10 | 3 days | 2026-10-13 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| hydroweb:201707 | Near normal (percentile 62) on 2026-10-13 | 10 days | 2026-10-26 |

### Exposure within 25 km of the station

WorldPop population (2020): 28,283, of which 5,551 at risk. Schools: 9 (0 at risk). Health facilities: 18 (2 at risk). Buildings (VIDA): 11,230 (41 at risk). Counties within 25 km: Baliet, Fashoda, Melut.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Kodok (Fashoda) | 10,878 (2,287) | 2,263 | 1 (0) | 6 (0) |
| Lul (Fashoda) | 5,110 (1,612) | 2,599 | 1 (0) | 2 (1) |
| Akoka (Baliet) | 3,315 (454) | 305 | 2 (0) | 1 (0) |
| Akotweng (Baliet) | 3,022 (277) | 507 | 0 (0) | 1 (0) |

# Longochuk County

Upper Nile | County population about 80,526 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 77 mm below median in the top metre (30-day rain 98% of normal); ~13 mm expected over 2 weeks = 17% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell possible (54%) on dry soils: monitor crops and pasture
• Exposure: County population about 81,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 31,000 | not listed | not listed | 15,000 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 2,917 |
| 2 (planning) | 4,538 |
| 3 (severe) | 8,752 |
| Displaced in the planning case | 1,263 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Guelguk | 3,433 | 2,935 | 5 (5) | 2 (2) | 1,581 (38) | 61.3 (49.9) |
| Dajo | 1,601 | 1,252 | 1 (1) | 2 (2) | 645 (11) | 41.3 (37.0) |
| Pamach | 1,287 | 945 | 2 (2) | 4 (4) | 1,125 (27) | 51.8 (42.8) |
| Longochuk | 250 | 220 | 2 (2) | 2 (2) | 363 (12) | 13.9 (8.6) |

Health facilities: 16 in the county, 15 on flood-prone ground | Schools: 16 in the county, 14 on flood-prone ground

## River level — nearest gauge: Baro km 4388

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 44 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:203704 | Below 2-yr level | 405.11 m | 0th | -0.002 m/day | 2026-10-09 |

# Luakpiny/Nasir County

Upper Nile | County population about 350,742 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 86 mm below median in the top metre (30-day rain 81% of normal); ~14 mm expected over 2 weeks = 16% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell possible (46%) on dry soils: monitor crops and pasture
• Exposure: County population about 351,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 20,000 | 3,402 | 13,800 | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 11,575 |
| 2 (planning) | 18,005 |
| 3 (severe) | 34,724 |
| Displaced in the planning case | 5,010 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Mading | 1,183 | 1,099 | 2 (2) | 2 (2) | 1,958 (43) | 24.2 (24.0) |
| Kiech Kuon | 1,872 | 1,064 | 10 (10) | 12 (11) | 4,553 (105) | 53.6 (38.3) |
| Maker | 931 | 916 | 1 (1) | 3 (3) | 1,411 (33) | 48.8 (48.6) |
| Jikmir | 413 | 412 | 6 (6) | 1 (1) | 2,311 (57) | 15.7 (15.4) |

Health facilities: 26 in the county, 25 on flood-prone ground | Schools: 29 in the county, 28 on flood-prone ground

## River level — nearest gauge: Baro km 4388

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 0 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:203704 | Below 2-yr level | 405.11 m | 0th | -0.002 m/day | 2026-10-09 |

# Maban County

Upper Nile | County population about 84,550 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 47 mm below median in the top metre (30-day rain 108% of normal); ~4 mm expected over 2 weeks = 8% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (96%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 85,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 31,452 | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 420 |
| 2 (planning) | 654 |
| 3 (severe) | 1,261 |
| Displaced in the planning case | 182 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Jinmakda | 5,089 | 4,893 | 1 (1) | 1 (1) | 5,402 (138) | 234.4 (231.3) |
| Boung | 2,297 | 2,046 | 5 (5) | 7 (6) | 22,483 (433) | 111.9 (103.6) |
| Banashowa | 1,875 | 1,776 | 1 (1) | 5 (5) | 3,060 (52) | 49.5 (48.7) |
| Jinkuata | 1,530 | 1,455 | 1 (1) | 11 (10) | 20,089 (356) | 52.1 (50.6) |

Health facilities: 25 in the county, 23 on flood-prone ground | Schools: 9 in the county, 9 on flood-prone ground

## River level — nearest gauge: R Adar km 3880

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: downstream of the county, about 55 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:107566 | Below 2-yr level | 387.24 m | 25th | +0.004 m/day | 2026-10-03 |

# Maiwut County

Upper Nile | County population about 147,823 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 73 mm below median in the top metre (30-day rain 84% of normal); ~16 mm expected over 2 weeks = 22% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell possible (30%) on dry soils: monitor crops and pasture
• Exposure: County population about 148,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 18,000 | not listed | 24,213 | 10,416 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 2,369 |
| 2 (planning) | 3,685 |
| 3 (severe) | 7,107 |
| Displaced in the planning case | 1,025 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Kigila | 1,058 | 757 | 0 (0) | 0 (0) | 178 (2) | 27.0 (24.9) |
| Olang | 775 | 694 | 0 (0) | 3 (3) | 806 (20) | 35.6 (29.6) |
| Jotoma | 927 | 691 | 1 (0) | 4 (2) | 624 (20) | 71.1 (58.9) |
| Maiwut | 544 | 506 | 3 (3) | 2 (2) | 257 (19) | 40.5 (35.9) |

Health facilities: 11 in the county, 9 on flood-prone ground | Schools: 4 in the county, 3 on flood-prone ground

## River level — nearest gauge: Baro km 4450

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 7 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:7821 | Below 2-yr level | 411.90 m | 12th | -0.002 m/day | 2026-10-05 |

# Malakal County

Upper Nile | County population about 204,041 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 61 mm below median in the top metre (30-day rain 106% of normal); ~3 mm expected over 2 weeks = 5% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (86%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 204,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 5,000 | not listed | not listed | 5,784 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 14,001 |
| 2 (planning) | 21,779 |
| 3 (severe) | 42,002 |
| Displaced in the planning case | 6,060 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Lelo | 535 | 229 | 18 (6) | 9 (2) | 12,747 (33) | 51.0 (15.6) |
| Ogot | 195 | 95 | 7 (0) | 1 (0) | 1,043 (7) | 29.8 (6.0) |
| Southern Malakal | 12 | 5 | 5 (2) | 1 (0) | 1,378 (12) | 5.3 (3.0) |
| Northern Malakal | 7 | 5 | 19 (4) | 3 (1) | 5,695 (23) | 2.9 (1.4) |

Health facilities: 16 in the county, 4 on flood-prone ground | Schools: 70 in the county, 18 on flood-prone ground

## River station: White Nile, River (dahiti:14196)

### River level status

Latest pass 2026-10-10: **Near normal** (percentile 62). Level 388.89 m; seasonal median 388.14 m; anomaly +0.74 m. Record: min 385.62 m, max 389.48 m, average 387.82 m.

Baseline: 10 years, 21 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.01 m; 27 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| dahiti:10179 | Insufficient record on 2016-05-20 | not established | n/a |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| dahiti:16323 | Unusually high (percentile 94) on 2026-10-03 | 14 days | 2026-10-24 |

### Exposure within 25 km of the station

WorldPop population (2020): 166,673, of which 102,828 at risk. Schools: 71 (24 at risk). Health facilities: 20 (5 at risk). Buildings (VIDA): 25,020 (212 at risk). Counties within 25 km: Baliet, Fashoda, Malakal, Panyikang.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Lelo (Malakal) | 84,096 (50,927) | 11,272 | 17 (5) | 9 (1) |
| Ogot (Malakal) | 55,491 (34,873) | 1,043 | 7 (1) | 1 (0) |
| Lul (Fashoda) | 13,220 (6,339) | 3,201 | 2 (0) | 3 (1) |
| Southern Malakal (Malakal) | 3,805 (3,520) | 1,378 | 5 (3) | 1 (0) |

# Manyo County

Upper Nile | County population about 83,853 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 35 mm below median in the top metre (30-day rain 132% of normal); ~0 mm expected over 2 weeks = 1% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (100%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 84,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 24,540 | 19,236 | 18,540 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 7,178 |
| 2 (planning) | 11,165 |
| 3 (severe) | 21,533 |
| Displaced in the planning case | 3,107 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Wedakona | 2,947 | 999 | 17 (10) | 4 (0) | 4,511 (28) | 132.2 (31.6) |
| Magenist | 894 | 494 | 0 (0) | 0 (0) | 1,212 (4) | 7.5 (5.1) |
| Kaka | 1,545 | 415 | 7 (2) | 4 (1) | 1,098 (6) | 156.1 (44.3) |
| Adhidwoi | 1,293 | 256 | 0 (0) | 6 (0) | 1,381 (4) | 78.7 (13.5) |

Health facilities: 14 in the county, 1 on flood-prone ground | Schools: 24 in the county, 12 on flood-prone ground

## River station: White Nile km 3623 (hydroweb:201336)

### River level status

Latest pass 2026-09-29: **Unusually high** (percentile 100). Level 383.77 m; seasonal median 383.49 m; anomaly +0.28 m. Record: min 381.94 m, max 384.35 m, average 383.35 m.

Baseline: 3 years, 7 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.26 m; 21 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| hydroweb:7970 | Above normal (percentile 77) on 2026-09-23 | 2 days | 2026-09-25 |

### Routed downstream signal

No downstream station linked.

### Exposure within 25 km of the station

WorldPop population (2020): 48,234, of which 25,483 at risk. Schools: 26 (11 at risk). Health facilities: 11 (2 at risk). Buildings (VIDA): 37,341 (149 at risk). Counties within 25 km: Manyo, Renk.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| North Renk (Renk) | 14,876 (8,203) | 28,311 | 14 (5) | 5 (0) |
| Geger (Renk) | 12,903 (8,762) | 2,017 | 9 (4) | 3 (1) |
| Wedakona (Manyo) | 9,640 (3,306) | 2,245 | 3 (2) | 1 (0) |
| Chemmedi (Renk) | 3,334 (1,804) | 63 | 0 (0) | 1 (0) |

# Melut County

Upper Nile | County population about 134,054 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 40 mm below median in the top metre (30-day rain 113% of normal); ~1 mm expected over 2 weeks = 3% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (100%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 134,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 14,872 | not listed | not listed | 21,135 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 8,403 |
| 2 (planning) | 13,071 |
| 3 (severe) | 25,208 |
| Displaced in the planning case | 3,637 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Wunamum | 2,069 | 2,002 | 1 (1) | 0 (0) | 3,716 (116) | 100.6 (95.0) |
| Paloch | 1,782 | 1,203 | 0 (0) | 2 (0) | 5,224 (35) | 137.4 (71.3) |
| Galdora | 1,128 | 481 | 9 (2) | 2 (1) | 782 (4) | 42.0 (19.5) |
| Bimachuk | 1,191 | 408 | 0 (0) | 0 (0) | 2,146 (23) | 59.4 (10.1) |

Health facilities: 6 in the county, 1 on flood-prone ground | Schools: 18 in the county, 4 on flood-prone ground

## River station: R Adar km 3864 (hydroweb:106194)

### River level status

Latest pass 2026-09-27: **Above normal** (percentile 69). Level 387.28 m; seasonal median 387.04 m; anomaly +0.24 m. Record: min 385.04 m, max 388.12 m, average 386.84 m.

Baseline: 7 years, 16 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.01 m; 27 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| hydroweb:107566 | Below normal (percentile 25) on 2026-10-03 | 0 days | 2026-10-03 |

### Routed downstream signal

No downstream station linked.

### Exposure within 25 km of the station

WorldPop population (2020): 24,416, of which 6,647 at risk. Schools: 12 (1 at risk). Health facilities: 9 (0 at risk). Buildings (VIDA): 11,001 (16 at risk). Counties within 25 km: Fashoda, Manyo, Melut.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Galdora (Melut) | 8,176 (2,561) | 717 | 9 (1) | 2 (0) |
| Paloch (Melut) | 7,846 (1,460) | 4,832 | 0 (0) | 2 (0) |
| Adhidwoi (Manyo) | 3,008 (509) | 1,255 | 0 (0) | 5 (0) |
| Melut (Melut) | 2,074 (338) | 3,881 | 1 (0) | 0 (0) |

# Panyikang County

Upper Nile | County population about 69,656 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 82 mm below median in the top metre (30-day rain 99% of normal); ~5 mm expected over 2 weeks = 6% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (76%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 70,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 31,000 | not listed | 39,680 | 15,140 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 5,059 |
| 2 (planning) | 7,870 |
| 3 (severe) | 15,178 |
| Displaced in the planning case | 2,190 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Kuel | 1,284 | 683 | 2 (0) | 1 (0) | 704 (0) | 43.5 (21.3) |
| Tonga | 1,207 | 557 | 0 (0) | 2 (0) | 1,735 (1) | 94.7 (32.8) |
| Dheteim | 821 | 506 | 0 (0) | 2 (0) | 1,344 (1) | 49.6 (29.5) |
| Panyikang | 766 | 483 | 0 (0) | 2 (0) | 606 (4) | 66.0 (30.6) |

Health facilities: 11 in the county, 0 on flood-prone ground | Schools: 5 in the county, 0 on flood-prone ground

## River station: White Nile, River (dahiti:17743)

### River level status

Latest pass 2026-09-23: **Unusually high** (percentile 100). Level 390.69 m; seasonal median 390.20 m; anomaly +0.49 m. Record: min 388.03 m, max 390.91 m, average 389.52 m.

Baseline: 7 years, 14 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.01 m; 27 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| dahiti:15557 | Unusually high (percentile 93) on 2026-09-25 | 0 days | 2026-09-25 |
| dahiti:19752 | Above normal (percentile 69) on 2026-08-29 | 0 days | 2026-08-29 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| dahiti:19751 | Near normal (percentile 62) on 2026-08-27 | 1 days | 2026-09-24 |

### Exposure within 25 km of the station

WorldPop population (2020): 59,720, of which 23,249 at risk. Schools: 14 (1 at risk). Health facilities: 17 (2 at risk). Buildings (VIDA): 6,262 (27 at risk). Counties within 25 km: Canal/Pigi, Fangak, Panyikang.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Atar (Canal/Pigi) | 23,609 (7,379) | 1,743 | 3 (0) | 4 (0) |
| Korwach (Canal/Pigi) | 12,186 (2,875) | 604 | 11 (1) | 3 (0) |
| Panyikang (Panyikang) | 8,306 (5,850) | 587 | 0 (0) | 2 (0) |
| Manajang (Fangak) | 5,555 (1,681) | 1,116 | 0 (0) | 2 (0) |

# Renk County

Upper Nile | County population about 210,351 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 39 mm below median in the top metre (30-day rain 128% of normal); ~0 mm expected over 2 weeks = 0% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (100%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 210,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 8,000 | 18,581 | not listed | 1,500 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 15,954 |
| 2 (planning) | 24,817 |
| 3 (severe) | 47,861 |
| Displaced in the planning case | 6,906 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Jalhak | 5,979 | 4,609 | 7 (3) | 2 (1) | 7,501 (48) | 426.5 (306.4) |
| Geger | 2,297 | 1,886 | 12 (8) | 10 (6) | 4,729 (79) | 180.6 (142.2) |
| North Renk | 950 | 745 | 14 (1) | 5 (1) | 28,715 (93) | 83.0 (57.1) |
| Chemmedi | 733 | 488 | 1 (1) | 3 (1) | 946 (17) | 64.7 (40.6) |

Health facilities: 20 in the county, 9 on flood-prone ground | Schools: 34 in the county, 13 on flood-prone ground

## River station: White Nile km 3670 (hydroweb:201337)

### River level status

Latest pass 2026-09-29: **Above normal** (percentile 83). Level 384.68 m; seasonal median 384.38 m; anomaly +0.30 m. Record: min 382.66 m, max 385.09 m, average 384.24 m.

Baseline: 3 years, 6 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.10 m; 21 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| hydroweb:202025 | Near normal (percentile 57) on 2026-09-29 | 3 days | 2026-10-02 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| hydroweb:7970 | Above normal (percentile 77) on 2026-09-23 | 0 days | 2026-09-29 |

### Exposure within 25 km of the station

WorldPop population (2020): 31,669, of which 12,612 at risk. Schools: 13 (11 at risk). Health facilities: 5 (2 at risk). Buildings (VIDA): 6,186 (46 at risk). Counties within 25 km: Manyo, Renk.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Jalhak (Renk) | 12,500 (4,698) | 1,848 | 2 (1) | 0 (0) |
| Chemmedi (Renk) | 9,862 (4,317) | 608 | 0 (0) | 1 (0) |
| Wedakona (Manyo) | 8,131 (3,403) | 3,615 | 11 (10) | 4 (2) |
| South Renk (Renk) | 1,174 (194) | 115 | 0 (0) | 0 (0) |

# Ulang County

Upper Nile | County population about 167,265 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 97 mm below median in the top metre (30-day rain 85% of normal); ~15 mm expected over 2 weeks = 15% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell possible (36%) on dry soils: monitor crops and pasture
• Exposure: County population about 167,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 5,205 |
| 2 (planning) | 8,096 |
| 3 (severe) | 15,614 |
| Displaced in the planning case | 2,253 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Kurmuot | 2,376 | 1,981 | 0 (0) | 3 (3) | 3,889 (94) | 39.8 (32.6) |
| Doma | 1,131 | 700 | 0 (0) | 2 (2) | 2,877 (60) | 56.5 (28.4) |
| Ulang | 925 | 605 | 0 (0) | 5 (5) | 5,741 (147) | 65.7 (45.2) |
| Yomding | 403 | 329 | 0 (0) | 2 (2) | 1,963 (36) | 36.8 (29.6) |

Health facilities: 12 in the county, 12 on flood-prone ground | Schools: 0 in the county, 0 on flood-prone ground

## River station: Sobat, River (dahiti:23359)

### River level status

Latest pass 2026-10-01: **Unusually high** (percentile 100). Level 399.68 m; seasonal median 399.32 m; anomaly +0.36 m. Record: min 394.06 m, max 399.99 m, average 397.61 m.

Baseline: 7 years, 30 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.01 m; 8 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| dahiti:19747 | Near normal (percentile 38) on 2026-09-23 | 23 days | 2026-10-16 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| dahiti:23358 | Below normal (percentile 27) on 2026-10-14 | 10 days | 2026-10-11 |

### Exposure within 25 km of the station

WorldPop population (2020): 98,991, of which 87,248 at risk. Schools: 19 (18 at risk). Health facilities: 18 (18 at risk). Buildings (VIDA): 12,789 (331 at risk). Counties within 25 km: Luakpiny/Nasir, Ulang.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Kurmuot (Ulang) | 21,743 (17,867) | 2,911 | 0 (0) | 2 (2) |
| Kiech Kuon (Luakpiny/Nasir) | 17,006 (16,467) | 1,182 | 6 (6) | 6 (6) |
| Kuerenge-Ke (Luakpiny/Nasir) | 15,958 (15,895) | 1,818 | 4 (3) | 2 (2) |
| Dingkar (Luakpiny/Nasir) | 15,186 (11,857) | 522 | 1 (1) | 3 (3) |

# Gogrial East County

Warrap | County population about 138,793 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 78 mm below median in the top metre (30-day rain 163% of normal); ~12 mm expected over 2 weeks = 15% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell possible (54%) on dry soils: monitor crops and pasture
• Exposure: County population about 139,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 46,583 | 25,218 | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 3,336 |
| 2 (planning) | 5,189 |
| 3 (severe) | 10,007 |
| Displaced in the planning case | 1,444 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Toch East | 2,109 | 1,843 | 11 (11) | 4 (3) | 16,426 (486) | 54.9 (53.9) |
| Pathuon West | 676 | 671 | 14 (14) | 6 (6) | 11,334 (343) | 13.6 (13.6) |
| Toch North | 588 | 564 | 8 (8) | 4 (4) | 5,863 (165) | 35.4 (35.2) |
| Pathuon East | 531 | 517 | 10 (9) | 4 (4) | 6,907 (241) | 37.5 (36.5) |

Health facilities: 21 in the county, 20 on flood-prone ground | Schools: 53 in the county, 52 on flood-prone ground

## River level — nearest gauge: Nahr Al Jur km 4456

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 0 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:203777 | Below 2-yr level | 403.47 m | 0th | -0.013 m/day | 2026-10-11 |

# Gogrial West County

Warrap | County population about 347,953 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 45 mm below median in the top metre (30-day rain 127% of normal); ~10 mm expected over 2 weeks = 23% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell possible (48%) on dry soils: monitor crops and pasture
• Exposure: County population about 348,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 13,000 | 71,821 | 48,828 | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 1,384 |
| 2 (planning) | 2,153 |
| 3 (severe) | 4,152 |
| Displaced in the planning case | 599 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Kuac North | 896 | 778 | 2 (2) | 7 (2) | 40,987 (n/a) | 43.7 (35.9) |
| Alek North | 702 | 673 | 3 (3) | 1 (1) | 9,521 (238) | 11.2 (11.2) |
| Kuac South | 614 | 566 | 2 (2) | 7 (7) | 15,446 (394) | 15.6 (14.5) |
| Gogrial | 538 | 405 | 11 (11) | 4 (0) | 13,275 (348) | 49.3 (38.4) |

Health facilities: 30 in the county, 18 on flood-prone ground | Schools: 44 in the county, 36 on flood-prone ground

## River level — nearest gauge: Lol km 4620

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: upstream of the county, about 2 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:203695 | Below 2-yr level | 412.13 m | 0th | +0.010 m/day | 2026-10-15 |

# Tonj East County

Warrap | County population about 190,959 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 70 mm below median in the top metre (30-day rain 80% of normal); ~19 mm expected over 2 weeks = 28% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Dry spell possible (30%) on dry soils: monitor crops and pasture
• Exposure: County population about 191,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 10,000 | 31,785 | 15,000 | 5,634 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 1,724 |
| 2 (planning) | 2,682 |
| 3 (severe) | 5,172 |
| Displaced in the planning case | 746 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Makuac | 700 | 700 | 3 (3) | 2 (2) | 4,487 (95) | 16.0 (16.0) |
| Palal | 671 | 663 | 6 (6) | 1 (1) | 4,900 (123) | 71.0 (70.6) |
| Ananatak | 607 | 603 | 4 (4) | 2 (2) | 3,148 (117) | 66.4 (65.7) |
| Wun-liit | 451 | 450 | 2 (2) | 1 (1) | 4,045 (120) | 42.5 (42.5) |

Health facilities: 12 in the county, 12 on flood-prone ground | Schools: 29 in the county, 29 on flood-prone ground

## River level — nearest gauge: Bahr Al Arab Trib 02 km 4435

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county's own sub-basin, about 9 km away (high confidence). Altimetry levels are "as seen by satellite" — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:104261 | Below 2-yr level | 394.37 m | 35th | +0.001 m/day | 2026-10-04 |

# Tonj North County

Warrap | County population about 271,487 | Issued 21 October 2026

## Advisory

- Dry spell possible (34%) on dry soils: monitor crops and pasture
- Exposure: County population about 271,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 12,207 | 30,000 | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 6,289 |
| 2 (planning) | 9,783 |
| 3 (severe) | 18,867 |
| Displaced in the planning case | 2,722 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Akop | 1,663 | 1,552 | 4 (4) | 2 (2) | 9,804 (252) | 86.7 (86.6) |
| Alabek | 1,592 | 1,513 | 6 (6) | 1 (1) | 14,953 (424) | 56.1 (56.1) |
| Aliek | 1,598 | 1,480 | 3 (3) | 2 (2) | 10,599 (302) | 35.2 (35.2) |
| Marial-lou | 1,352 | 1,339 | 6 (6) | 3 (1) | 3,229 (102) | 36.0 (36.0) |

Health facilities: 21 in the county, 19 on flood-prone ground | Schools: 59 in the county, 59 on flood-prone ground

## River station: Unknown, River (dahiti:2687)

### River level status

Latest pass 2026-09-11: **Above normal** (percentile 88). Level 392.97 m; seasonal median 392.63 m; anomaly +0.34 m. Record: min 391.50 m, max 393.19 m, average 392.55 m.

Baseline: 10 years, 57 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.00 m; 10 days since previous pass.

### Routed upstream signal

| Upstream station | Status (latest pass) | Median travel time | Expected here around |
|---|---|---|---|
| dahiti:39376 | Below normal (percentile 27) on 2026-09-28 | 38 days | 2026-11-05 |

### Routed downstream signal

| Downstream station | Status (latest pass) | Median travel time from here | This station's signal expected there around |
|---|---|---|---|
| dahiti:2688 | Near normal (percentile 65) on 2026-09-11 | 4 days | 2026-09-15 |

### Exposure within 25 km of the station

WorldPop population (2020): 22,689, of which 17,663 at risk. Schools: 1 (0 at risk). Health facilities: 0 (0 at risk). Buildings (VIDA): 203 (7 at risk). Counties within 25 km: Koch, Mayom, Tonj North.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Akop (Tonj North) | 8,440 (7,417) | 123 | 0 (0) | 0 (0) |
| Alabek (Tonj North) | 5,717 (5,128) | 69 | 0 (0) | 0 (0) |
| Pakur (Koch) | 4,902 (3,152) | 9 | 1 (0) | 0 (0) |
| Riak (Mayom) | 3,629 (1,966) | 2 | 0 (0) | 0 (0) |

# Tonj South County

Warrap | County population about 126,289 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 66 mm below median in the top metre (30-day rain 170% of normal); ~32 mm expected over 2 weeks = 48% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Exposure: County population about 126,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 16,693 | 15,600 | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 472 |
| 2 (planning) | 734 |
| 3 (severe) | 1,416 |
| Displaced in the planning case | 204 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Tonj | 5,090 | 4,284 | 12 (12) | 5 (5) | 19,583 (562) | 450.3 (397.2) |
| Manyang-ngok | 878 | 851 | 7 (6) | 2 (2) | 6,179 (168) | 150.9 (143.7) |
| Wath-alel | 835 | 825 | 0 (0) | 3 (3) | 6,184 (179) | 15.2 (15.2) |
| Thiet | 363 | 347 | 0 (0) | 2 (2) | 9,482 (300) | 68.2 (65.5) |

Health facilities: 13 in the county, 13 on flood-prone ground | Schools: 19 in the county, 18 on flood-prone ground

## River level — nearest gauge: Unknown, River

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county’s own sub-basin, about 30 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| dahiti:2686 | Below 2-yr level | 474.92 m | 0th | -0.016 m/day | 2026-09-11 |

# Twic County

Warrap | County population about 291,675 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 65 mm below median in the top metre (30-day rain 131% of normal); ~6 mm expected over 2 weeks = 9% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (70%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 292,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 29,044 | 24,000 | 4,944 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 15,501 |
| 2 (planning) | 24,112 |
| 3 (severe) | 46,502 |
| Displaced in the planning case | 6,709 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Wunrok | 846 | 799 | 22 (22) | 7 (7) | 25,922 (839) | 34.5 (28.1) |
| Turalei | 812 | 792 | 10 (10) | 9 (9) | 21,496 (617) | 65.1 (64.3) |
| Aweeng | 770 | 690 | 9 (9) | 8 (8) | 9,721 (296) | 49.7 (45.8) |
| Ajak-kuac | 431 | 415 | 7 (7) | 3 (3) | 7,376 (202) | 12.7 (11.5) |

Health facilities: 43 in the county, 38 on flood-prone ground | Schools: 78 in the county, 61 on flood-prone ground

## River station: Lol Trib01 km 4417 (hydroweb:103547)

### River level status

Latest pass 2026-09-30: **Near normal** (percentile 34). Level 400.40 m; seasonal median 400.49 m; anomaly -0.09 m. Record: min 399.41 m, max 401.01 m, average 400.27 m.

Baseline: 10 years, 22 passes within ±30 days, 2016–2025. Quality: ok; uncertainty ±0.35 m; 27 days since previous pass.

### Routed downstream signal

No downstream station linked.

### Exposure within 25 km of the station

WorldPop population (2020): 104,120, of which 99,678 at risk. Schools: 36 (36 at risk). Health facilities: 19 (19 at risk). Buildings (VIDA): 44,244 (n/a at risk). Counties within 25 km: Gogrial East, Mayom, Twic.

| Payam (county) | Population (at risk) | Buildings | Schools (at risk) | Health (at risk) |
|---|---|---|---|---|
| Aweeng (Twic) | 35,690 (32,408) | 9,721 | 9 (9) | 8 (8) |
| Turalei (Twic) | 33,741 (33,049) | 18,784 | 9 (9) | 7 (7) |
| Wunrok (Twic) | 24,689 (24,661) | 13,571 | 14 (14) | 2 (2) |
| Ajak-kuac (Twic) | 8,304 (8,152) | 2,183 | 4 (4) | 2 (2) |

# Jur River County

Western Bahr el Ghazal | County population about 293,840 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 63 mm below median in the top metre (30-day rain 139% of normal); ~26 mm expected over 2 weeks = 41% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Exposure: County population about 294,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | 10,000 | 8,767 | 26,850 | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 1,144 |
| 2 (planning) | 1,779 |
| 3 (severe) | 3,431 |
| Displaced in the planning case | 495 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Kuajiena | 4,408 | 3,475 | 9 (7) | 6 (4) | 12,868 (222) | 262.1 (207.7) |
| Kangi | 1,905 | 1,461 | 1 (0) | 9 (7) | 8,207 (129) | 100.5 (81.5) |
| Rocrocdong | 1,378 | 1,168 | 19 (14) | 4 (4) | 7,536 (143) | 137.9 (119.7) |
| Udici | 1,487 | 1,062 | 6 (5) | 7 (4) | 8,096 (128) | 136.1 (107.2) |

Health facilities: 43 in the county, 34 on flood-prone ground | Schools: 53 in the county, 43 on flood-prone ground

## River level — nearest gauge: Jur km 4780

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county's own sub-basin, about 0 km away (high confidence). Altimetry levels are "as seen by satellite" — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:102830 | Below 2-yr level | 441.15 m | 0th | -0.027 m/day | 2026-09-26 |

# Raja County

Western Bahr el Ghazal | County population about 76,633 | Issued 21 October 2026

## Advisory

• CROP/PASTURE STRESS (severe): soil about 70 mm below median in the top metre (30-day rain 99% of normal); ~15 mm expected over 2 weeks = 21% of the deficit. Protect water sources, plan livestock watering and grazing moves, favour short-cycle and drought-tolerant crops
• Dry spell likely (60%): suitable for weeding, harvesting and drying; delay planting
• Exposure: County population about 77,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 340 |
| 2 (planning) | 529 |
| 3 (severe) | 1,020 |
| Displaced in the planning case | 147 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Ere | 23,780 | 13,725 | 0 (0) | 1 (1) | 6,470 (100) | 633.8 (369.9) |
| Uyujuku | 19,851 | 7,825 | 5 (0) | 5 (1) | 3,820 (16) | 551.5 (223.4) |
| Raga | 7,748 | 4,670 | 12 (3) | 4 (1) | 6,371 (59) | 353.2 (204.9) |
| Ringi | 10,632 | 4,400 | 6 (2) | 5 (2) | 1,189 (7) | 124.7 (52.3) |

Health facilities: 15 in the county, 5 on flood-prone ground | Schools: 23 in the county, 5 on flood-prone ground

## River level — nearest gauge: Wadi Boro, River

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: downstream of the county, about 7 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| dahiti:23344 | Below 2-yr level | 466.07 m | 7th | -0.007 m/day | 2026-09-05 |

# Wau County

Western Bahr el Ghazal | County population about 345,948 | Issued 21 October 2026

## Advisory

• Soil moisture deficit (moderate): soil about 43 mm below median in the top metre (30-day rain 136% of normal); ~31 mm expected over 2 weeks = 71% of the deficit. Monitor crops and pasture; delay new planting until soils recover
• Exposure: County population about 346,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 5,398 |
| 2 (planning) | 8,397 |
| 3 (severe) | 16,194 |
| Displaced in the planning case | 2,337 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Bagari | 11,417 | 5,630 | 25 (10) | 9 (4) | 5,104 (70) | 245.9 (133.6) |
| Kpaile | 4,651 | 2,806 | 9 (8) | 5 (4) | 1,729 (18) | 160.8 (131.1) |
| Besselia | 3,072 | 1,517 | 16 (9) | 12 (7) | 2,966 (55) | 231.3 (132.4) |
| Wau South | 50 | 44 | 62 (39) | 13 (9) | 41,799 (n/a) | 21.8 (19.3) |

Health facilities: 47 in the county, 31 on flood-prone ground | Schools: 188 in the county, 122 on flood-prone ground

## River level — nearest gauge: Jur km 4808

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: upstream of the county, about 0 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:111154 | Below 2-yr level | 446.60 m | 0th | +0.004 m/day | 2026-10-11 |

# Ezo County

Western Equatoria | County population about 138,291 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 40 mm below median in the top metre (30-day rain 116% of normal); ~67 mm expected over 2 weeks = 167% of the deficit. Soils should recover if the rain arrives
• Exposure: About 0 people live on ground that has flooded before (of ~138,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 600 | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 550 |
| 2 (planning) | 855 |
| 3 (severe) | 1,649 |
| Displaced in the planning case | 238 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Yangiri | 4,774 | 2,660 | 5 (1) | 4 (1) | 1,145 (10) | 138.8 (80.7) |
| Bagidi | 1,230 | 598 | 3 (1) | 2 (0) | 718 (5) | 106.8 (52.8) |
| Naandi | 906 | 336 | 7 (1) | 9 (0) | 1,190 (6) | 91.4 (33.4) |
| Bariguna | 539 | 296 | 1 (1) | 1 (0) | 585 (4) | 29.3 (15.1) |

Health facilities: 30 in the county, 7 on flood-prone ground | Schools: 32 in the county, 8 on flood-prone ground

## River level — nearest gauge: Jur km 4964

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: downstream of the county, about 0 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:108192 | Below 2-yr level | 483.47 m | 0th | +0.007 m/day | 2026-10-06 |

# Ibba County

Western Equatoria | County population about 68,544 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 42 mm below median in the top metre (30-day rain 103% of normal); ~69 mm expected over 2 weeks = 166% of the deficit. Soils should recover if the rain arrives
• Exposure: County population about 69,000

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 7,524 | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 260 |
| 2 (planning) | 405 |
| 3 (severe) | 781 |
| Displaced in the planning case | 113 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Manikakara | 4,144 | 2,855 | 5 (3) | 3 (1) | 2,916 (30) | 173.9 (121.1) |
| Maruko | 2,864 | 1,973 | 0 (0) | 2 (0) | 67 (0) | 74.3 (50.3) |
| Ibba Centre | 977 | 544 | 4 (1) | 5 (2) | 7,277 (117) | 66.3 (31.7) |
| Madebe | 763 | 537 | 1 (0) | 2 (0) | 711 (3) | 63.1 (35.9) |

Health facilities: 14 in the county, 4 on flood-prone ground | Schools: 13 in the county, 4 on flood-prone ground

## River level — nearest gauge: Ibba km 4410

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county’s own sub-basin, about 70 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:111296 | Below 2-yr level | 475.10 m | 0th | -0.007 m/day | 2026-10-11 |

# Maridi County

Western Equatoria | County population about 113,864 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 47 mm below median in the top metre (30-day rain 103% of normal); ~69 mm expected over 2 weeks = 148% of the deficit. Soils should recover if the rain arrives

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 429 |
| 2 (planning) | 668 |
| 3 (severe) | 1,288 |
| Displaced in the planning case | 186 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Kozi | 3,075 | 2,363 | 8 (3) | 4 (3) | 1,736 (22) | 250.7 (198.7) |
| Mambe | 2,796 | 1,610 | 8 (5) | 6 (3) | 3,266 (42) | 178.6 (111.6) |
| Ngamunde | 602 | 320 | 2 (0) | 4 (1) | 1,985 (18) | 56.5 (29.8) |
| Landili | 808 | 267 | 1 (0) | 3 (0) | 384 (2) | 58.8 (15.7) |

Health facilities: 29 in the county, 12 on flood-prone ground | Schools: 36 in the county, 16 on flood-prone ground

## River level — nearest gauge: Yei km 4848

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 40 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:203361 | Below 2-yr level | 628.27 m | 0th | -0.014 m/day | 2026-10-10 |

# Mundri East County

Western Equatoria | County population about 103,283 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 30 mm below median in the top metre (30-day rain 145% of normal); ~53 mm expected over 2 weeks = 177% of the deficit. Soils should recover if the rain arrives
• Exposure: About 0 people live on ground that has flooded before (of ~103,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 29,946 | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 402 |
| 2 (planning) | 625 |
| 3 (severe) | 1,205 |
| Displaced in the planning case | 174 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Kediba | 1,426 | 1,249 | 6 (5) | 6 (5) | 7,040 (118) | 133.8 (114.9) |
| Witto | 1,382 | 1,046 | 7 (5) | 3 (2) | 6,197 (79) | 108.1 (80.1) |
| Minga | 802 | 700 | 5 (5) | 2 (2) | 1,709 (28) | 30.1 (26.7) |
| Lozoh | 918 | 653 | 11 (7) | 4 (2) | 8,501 (125) | 90.8 (62.9) |

Health facilities: 16 in the county, 12 on flood-prone ground | Schools: 35 in the county, 28 on flood-prone ground

## River level — nearest gauge: Yei km 4848

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 0 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:203361 | Below 2-yr level | 628.27 m | 0th | -0.014 m/day | 2026-10-10 |

# Mundri West County

Western Equatoria | County population about 51,413 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 40 mm below median in the top metre (30-day rain 138% of normal); ~61 mm expected over 2 weeks = 153% of the deficit. Soils should recover if the rain arrives
• Exposure: About 0 people live on ground that has flooded before (of ~51,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 41,374 | 1,530 | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 191 |
| 2 (planning) | 297 |
| 3 (severe) | 573 |
| Displaced in the planning case | 83 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Kotobi | 2,200 | 1,573 | 6 (4) | 5 (4) | 3,398 (54) | 125.6 (95.9) |
| Mundri | 1,775 | 1,397 | 12 (9) | 3 (2) | 11,801 (273) | 82.8 (68.6) |
| Bangolo | 1,224 | 815 | 1 (1) | 7 (4) | 1,624 (17) | 76.7 (52.0) |
| Amadi | 675 | 552 | 5 (3) | 3 (3) | 2,450 (58) | 76.2 (60.6) |

Health facilities: 18 in the county, 13 on flood-prone ground | Schools: 24 in the county, 17 on flood-prone ground

## River level — nearest gauge: Yei km 4779

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county’s own sub-basin, about 0 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:105342 | Below 2-yr level | 543.31 m | 7th | -0.028 m/day | 2026-09-23 |

# Mvolo County

Western Equatoria | County population about 77,611 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 49 mm below median in the top metre (30-day rain 144% of normal); ~47 mm expected over 2 weeks = 97% of the deficit. Soils should recover if the rain arrives
• Exposure: About 0 people live on ground that has flooded before (of ~78,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | 31,959 | not listed | 15,780 |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 3,036 |
| 2 (planning) | 4,723 |
| 3 (severe) | 9,109 |
| Displaced in the planning case | 1,314 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Bagori | 1,645 | 1,429 | 0 (0) | 2 (2) | 974 (19) | 72.4 (57.1) |
| Yeri | 1,326 | 1,187 | 0 (0) | 1 (1) | 1,053 (43) | 94.7 (81.2) |
| Mvolo | 577 | 530 | 1 (1) | 1 (1) | 5,600 (76) | 49.0 (44.2) |
| Bahr El Grindi | 582 | 518 | 2 (2) | 3 (2) | 1,450 (26) | 34.5 (31.0) |

Health facilities: 12 in the county, 8 on flood-prone ground | Schools: 7 in the county, 7 on flood-prone ground

## River level — nearest gauge: Gulnam km 4669

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: in the county’s own sub-basin, about 53 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:104259 | Below 2-yr level | 424.08 m | 0th | -0.006 m/day | 2026-10-04 |

# Nagero County

Western Equatoria | County population about 61,561 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 39 mm below median in the top metre (30-day rain 161% of normal); ~50 mm expected over 2 weeks = 126% of the deficit. Soils should recover if the rain arrives

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 265 |
| 2 (planning) | 412 |
| 3 (severe) | 795 |
| Displaced in the planning case | 115 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Nagero | 9,197 | 5,420 | 7 (2) | 8 (4) | 2,224 (24) | 356.8 (247.4) |
| Namutina | 8,763 | 2,973 | 5 (1) | 13 (3) | 2,309 (15) | 209.9 (58.3) |

Health facilities: 21 in the county, 7 on flood-prone ground | Schools: 12 in the county, 3 on flood-prone ground

## River level — nearest gauge: Jur km 4964

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 8 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:108192 | Below 2-yr level | 483.47 m | 0th | +0.007 m/day | 2026-10-06 |

# Nzara County

Western Equatoria | County population about 86,370 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 43 mm below median in the top metre (30-day rain 118% of normal); ~69 mm expected over 2 weeks = 158% of the deficit. Soils should recover if the rain arrives

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | 1,125 | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 319 |
| 2 (planning) | 496 |
| 3 (severe) | 957 |
| Displaced in the planning case | 138 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Ringasi | 4,433 | 2,872 | 2 (1) | 1 (1) | 945 (9) | 84.8 (52.2) |
| Basukangbi | 714 | 251 | 2 (0) | 2 (0) | 307 (4) | 55.3 (17.3) |
| Nzara Centre | 416 | 225 | 14 (1) | 8 (0) | 17,025 (207) | 48.6 (25.2) |
| Sakure | 491 | 223 | 3 (0) | 4 (0) | 3,815 (42) | 47.3 (18.1) |

Health facilities: 19 in the county, 1 on flood-prone ground | Schools: 25 in the county, 2 on flood-prone ground

## River level — nearest gauge: Jur km 4973

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: downstream of the county, about 23 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:108191 | Below 2-yr level | 484.60 m | 0th | +0.018 m/day | 2026-10-06 |

# Tambura County

Western Equatoria | County population about 122,913 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 34 mm below median in the top metre (30-day rain 117% of normal); ~57 mm expected over 2 weeks = 167% of the deficit. Soils should recover if the rain arrives

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 478 |
| 2 (planning) | 744 |
| 3 (severe) | 1,435 |
| Displaced in the planning case | 207 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Tambura | 1,710 | 980 | 10 (0) | 15 (3) | 17,008 (110) | 71.3 (37.9) |
| Mupoi | 1,563 | 965 | 7 (3) | 3 (1) | 1,834 (12) | 66.0 (38.5) |
| Source Yubu | 418 | 146 | 7 (2) | 5 (0) | 2,780 (12) | 56.7 (21.4) |

Health facilities: 23 in the county, 4 on flood-prone ground | Schools: 24 in the county, 5 on flood-prone ground

## River level — nearest gauge: Jur km 4973

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: downstream of the county, about 0 km away (high confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:108191 | Below 2-yr level | 484.60 m | 0th | +0.018 m/day | 2026-10-06 |

# Yambio County

Western Equatoria | County population about 173,972 | Issued 21 October 2026

## Advisory

• Soil moisture deficit easing: soil about 41 mm below median in the top metre (30-day rain 116% of normal); ~70 mm expected over 2 weeks = 171% of the deficit. Soils should recover if the rain arrives
• Exposure: About 0 people live on ground that has flooded before (of ~174,000 in the county)

## People affected by floods, previous assessments (county)

| Year | 2021 | 2022 | 2024 | 2025 |
|---|---|---|---|---|
| People affected | not listed | not listed | not listed | not listed |

## Flood scenarios, 2026 Floods & Drought Plan (county, people affected)

| Scenario | People affected |
|---|---|
| 1 (lower) | 656 |
| 2 (planning) | 1,021 |
| 3 (severe) | 1,969 |
| Displaced in the planning case | 284 |

Planning figures, not forecasts or probabilities. Scenarios 1 and 3 apply the plan's state coefficients to the county planning case.

## Infrastructure at risk of flooding, by payam (flood-prone ground)

At risk = flooded now or in at least 15% of years in the same season (Sentinel-1, 2020–2025).

| Payam | Payam area km² | At risk km² | Schools (at risk) | Health (at risk) | Buildings (at risk) | Roads km (at risk) |
|---|---|---|---|---|---|---|
| Nadiangere | 4,096 | 2,770 | 0 (0) | 2 (0) | 282 (6) | 185.9 (133.0) |
| Bangasu | 2,183 | 1,237 | 10 (4) | 10 (1) | 7,661 (58) | 189.6 (99.0) |
| Ri-rangu | 1,363 | 751 | 3 (3) | 5 (3) | 1,039 (15) | 95.2 (47.1) |
| Yambio Town | 555 | 328 | 36 (1) | 26 (4) | 72,009 (n/a) | 71.4 (40.3) |

Health facilities: 52 in the county, 10 on flood-prone ground | Schools: 60 in the county, 12 on flood-prone ground

## River level — nearest gauge: Ibba km 4410

No altimetry station falls within 25 km of this county, so this is the most relevant gauge on its river network: audit-override, about 21 km away (medium confidence). Altimetry levels are “as seen by satellite” — an indicator of the river's state, not a local reading for the county.

| Gauge | Status (latest pass) | Water level | Seasonal pct. | Trend | Last pass |
|---|---|---|---|---|---|
| hydroweb:111296 | Below 2-yr level | 475.10 m | 0th | -0.007 m/day | 2026-10-11 |

# About this report: data, methods and references

Decision support, not an official warning. Alert levels follow the impact-based likelihood x impact approach of WMO-No. 1150; the scales are provisional. Figures are planning and monitoring information and carry the uncertainties listed below.

## 1. How the report is produced

A GitHub Actions workflow runs the county bulletin twice a day, after the ECMWF 00 and 12 UTC releases (11:30 and 23:30 Juba). The combined report is rebuilt from that bulletin after the evening run (midnight Juba), emailed to subscribers as one PDF and published as the latest report linked from the live map. A weekly Earth Engine job refreshes the flood extent, the infrastructure-at-risk table and the 25 km station exposure. The weekly version label (vDDMMYY) is the Monday of the issue week; the first is v51026 (5 Oct 2026).

## 2. County indicators and alert levels

**Rain so far:** GSMaP v8 gauge-corrected rainfall, 7, 15 and 30-day totals against the same dates 2001–2025. **Soil and water balance:** NASA SMAP Level-4 root-zone soil moisture, evapotranspiration and runoff against 2015–2025; wetness is judged by the root-zone z-score (steadier than a percentile with about ten comparison years that include the flood years 2019–2022 and 2024). The soil deficit is the root-zone water missing against the median, in mm. **Outlook:** ECMWF IFS ensemble (up to 51 members, 15 days); chances of a 7-day dry spell, a 3-day wet spell and 50 mm in week 1 are the share of members that show the event. **Alert level:** likelihood x impact (green no action, yellow be aware, orange be prepared, red take action), for the hazard (drought / dry spell or flood / waterlogging) named in each county advisory; the likelihood and impact ratings are shown in the advisory text.

Forecast check against observed rain: days 1–5, 14220 county-days: hit rate 85%, false-alarm ratio 55%, Brier skill -0.28.

## 3. Cover lists

**Drought watch:** counties with the lowest root-zone soil moisture that the next 2 weeks of rain will not fix. **Flood watch:** wettest soil, water surplus and heavy rain ahead, weighted by people on flood-prone ground. **Gauge watch:** stations where the water takes more than 5 days to reach the next station downstream and the last pass is newer than that travel time, so there is still time to warn downstream counties (star = a station already on the watch list). **Towns and counties to monitor:** red or orange counties not already in the drought or flood lists.

## 4. Flood history, scenarios and settlements

People affected in 2021, 2022, 2024 and 2025 come from the flood assessments compiled for the project (county totals; "not listed" means the county does not appear in that assessment, not that nobody was affected). The 2026 scenarios are planning figures from the 2026 Floods and Drought Plan (scenario 1 lower, 2 planning, 3 severe, and people displaced in the planning case); scenarios 1 and 3 apply the plan's state coefficients to the county planning case and are not forecasts or probabilities. Settlements are those assessed in September 2025 (OCHA 2024 and UNMISS 2025 high-ground list, other flooded settlements and small towns), grouped by payam. Population is the 2025 county estimate supplied to the project.

## 5. Infrastructure at risk, by payam

**At risk** = flooded in the current maximum flood extent, or flooded in at least 15% of the same-season baseline years (2020–2025) where at least three baseline years exist. The baseline is Sentinel-1 (descending VV): open water below -18 dB after a 50 m focal median, plus flooded vegetation where VV rises at least 3 dB over the Feb–Mar dry-season median, limited to terrain within 15 m above the nearest drainage (MERIT Hydro HAND). The current extent is the maximum over the latest 12 days of Sentinel-1, exported every Sunday to a fixed Earth Engine asset. Counts are per payam (512 payam polygons): schools and health facilities (OCHA point layers, counted when the point falls on at-risk ground), buildings (VIDA Google-Microsoft combined footprints; at-risk count skipped where a payam has more than 40,000), roads (GRIP4, 100 m raster, length on at-risk ground) and area. County totals are the sum of its payams.

## 6. River stations

Levels are satellite-altimetry passes from DAHITI (DGFI-TUM) and Hydroweb.Next (Theia / CNES, LEGOS), merged nightly with quality flags (jumps checked against neighbours, long gaps, high uncertainty). The **status** compares the latest level with passes within ±30 days of the same date in 2016–2025: unusually high from the 70th percentile, above normal 60th–70th, near normal 40th–60th, below normal 30th–40th, unusually low below the 30th; fewer than 2 years or 6 passes counts as insufficient record. Low and insufficient stations are not shown. The **routed signal** reads the linked upstream and downstream stations: the median travel time is the typical lag between the two stations over their overlapping passes, and "expected here around" is the observation date plus that lag. Altimetry samples a river every 10–35 days, so a pass can miss a peak, and flood-level thresholds are "as seen by the satellite", not gauge return periods.

## 7. Exposure within 25 km of a station

Population (WorldPop 2020, 100 m), schools, health facilities and VIDA buildings inside a 25 km circle around the station, with the share on at-risk ground (definition in section 5) and a payam-by-payam breakdown of the part of each payam inside the circle. Circles overlap neighbouring counties, which are listed. A station is assigned to the county that contains it.

## 8. News

Reported news comes from Eye Radio, Radio Tamazuj, Sudans Post, UN and ReliefWeb items collected by the climate-news monitor and stored in data/news.json. Each county page lists items from the last 21 days that name

that county; items naming no county appear on the cover. Items are summarised, not quoted; single-source items are unverified and county names may be inferred from places. Media coverage is partial and Facebook is not covered.

## 9. Main limits

• Rain, soil and flood layers are satellite products: coarse (GSMaP about 10 km, SMAP L4 about 9 km) and subject to retrieval error, especially in wetlands.
• The ensemble gives chances, not certainties; the dry-spell and heavy-rain chances are for the county as a whole.
• Flood extent from radar misses flooding under dense canopy and can over-detect on wet floodplain vegetation; the weekly window can miss short events.
• Population, building and facility layers are modelled or compiled, and may be out of date or incomplete in remote areas.
• River flooding from upstream can continue while local soils are dry: the land model does not include river overflow.
• Assessment and scenario figures describe past or planned situations, not the situation now.

## Data sources

| Layer | Source | Used for |
|---|---|---|
| Rainfall | GSMaP v8 operational, gauge-corrected (JAXA), via Google Earth Engine | Rain so far, anomalies |
| Soil moisture, ET, runoff | NASA SMAP Level-4 SPL4SMGP | Soil z-score, deficit, water balance |
| Forecast | ECMWF IFS ensemble open data (CC BY 4.0, © ECMWF) | Dry / wet spell and heavy-rain chances |
| Forecast rain, 7-day | NOAA GFS 0.25°; ECMWF IFS NRT; CHIRPS daily (UCSB-CHG) | Station rainfall outlook in the app |
| River levels | DAHITI (DGFI-TUM); Hydroweb.Next (Theia / CNES, LEGOS) | Station status and routed signals |
| River discharge outlook | GEOGLOWS ECMWF Streamflow Model (BYU / ECMWF) | River alert, where available |
| Flood extent and baseline | Copernicus Sentinel-1 GRD; MERIT Hydro HAND | Current and same-season flood extent |
| Flood-prone ground | JRC Global Surface Water; Global Flood Database | Flood-prone share of population |
| Population | County estimates 2025 (project); WorldPop 2020, 100 m (Univ. of Southampton, CC BY 4.0) | County and 25 km population |
| Settlement and buildings | GHSL built-up surface (JRC); VIDA combined footprints; JRC GHS-OBAT 2020 | Built-up area, building counts |
| Roads | GRIP4 Africa (Meijer et al. 2018) | Road length at risk |
| Schools, health facilities | OCHA (data.humdata.org/group/ssd) | Facilities at risk |
| Cropland | ESA WorldCover 2021 v200 (CC BY 4.0) | Cropland in the county bulletin |
| Catchments | HydroBASINS / HydroSHEDS | Upstream catchment rainfall |
| Admin boundaries | OCHA (data.humdata.org/group/ssd); 512 payams | All county and payam figures |
| Flood assessments, scenarios | Flood assessments 2021–2025; 2026 Floods and Drought Plan; OCHA 2024 / UNMISS 2025 settlement list | Earlier assessments, scenarios, settlements |

## Key references

• Gorelick, N. et al. (2017). Google Earth Engine: planetary-scale geospatial analysis for everyone. Remote Sensing of Environment 202, 18–27.
• Pekel, J.-F. et al. (2016). High-resolution mapping of global surface water and its long-term changes. Nature 540, 418–422.
• Tellman, B. et al. (2021). Satellite imaging reveals increased proportion of population exposed to floods. Nature 596, 80–86.
• Torres, R. et al. (2012). GMES Sentinel-1 mission. Remote Sensing of Environment 120, 9–24.
• Yamazaki, D. et al. (2019). MERIT Hydro: a high-resolution global hydrography map based on latest topography datasets. Water Resources Research 55, 5053–5073.
• Schwatke, C. et al. (2015). DAHITI: an innovative approach for estimating water level time series over inland waters using multi-mission satellite altimetry. Hydrology and Earth System Sciences 19, 4345–4364.
• Lehner, B. and Grill, G. (2013). Global river hydrography and network routing (HydroSHEDS, HydroBASINS). Hydrological Processes 27, 2171–2186.
• Meijer, J. R. et al. (2018). Global patterns of current and future road infrastructure. Environmental Research Letters 13, 064006.
• Zanaga, D. et al. (2022). ESA WorldCover 10 m 2021 v200. Zenodo.
• Gumbel, E. J. (1958). Statistics of Extremes. Columbia University Press.
• World Meteorological Organization (2015). WMO Guidelines on Multi-hazard Impact-based Forecast and Warning Services, WMO-No. 1150.
• Data providers: OCHA (schools, health facilities, administrative boundaries; data.humdata.org/group/ssd), JAXA (GSMaP), NASA (SMAP L4), ECMWF (IFS ensemble), NOAA (GFS), UCSB Climate Hazards Center (CHIRPS), DGFI-TUM (DAHITI), CNES / LEGOS (Hydroweb.Next), BYU / ECMWF (GEOGLOWS), University of Southampton (WorldPop), European Commission JRC (GSW, GHSL, GHS-OBAT), VIDA / Google / Microsoft (building footprints), ESA (WorldCover, Sentinel-1).

## Method code and the live map

Pipeline code: github.com/Penuelabi/altimetry-nightly. Live map: https://penuelabi.users.earthengine.app/view/south-sudan-weather-forecast. Prepared by ALLAU, Denis Abi, PhD, Abuk Project, Mayardit Academy for Space Sciences, University of Juba and University of California, Davis.